




RED ROCKS COMMUNITY COLLEGE

13300 W 6th Ave.
Lakewood, CO 80228

GENERATOR ADDITION CONSTRUCTION DOCUMENTS OCTOBER 20, 2025



DRAWING INDEX	
DRAWING NO.	DISCIPLINE AND DRAWING DESCRIPTION
G00	COVER SHEET
GENERAL	
C1.0	CIVIL NOTES
C1.1	CIVIL EXISTING CONDITONS PLAN
C1.2	CIVIL GRADING AND EROSION CONTROL PLAN
C1.3	CIVIL EROSION CONTROL DETAILS
C1.4	CIVIL EROSION CONTROL DETAILS
STRUCTURAL	
S1.0	STRUCTURAL PLANS DETAILS AND NOTES
MECHANICAL	
M00	MECHANICAL LEGEND
M01	MECHANICAL SITE PLAN
M60	MECHANICAL SCHEDULES
ELECTRICAL	
E00	ELECTRICAL LEGEND
E01	ELECTRICAL SITE PLAN
E10	ELECTRICAL FLOOR PLAN
ED50	ELECTRICAL DEMO ONE-LINE DIAGRAM
E50	ELECTRICAL ONE-LINE DIAGRAM
E51	ELECTRICAL DETAILS
E60	ELECTRICAL SCHEDULES

APPLICABLE CODES	
AHJ: STATE OF COLORADO	
FIRE AUTHORITY: WEST METRO FIRE DISTRICT	
REMODEL	<input checked="" type="checkbox"/> NEW <input type="checkbox"/>
YEAR	CODE
2021	INTERNATIONAL BUILDING CODE
2021	INTERNATIONAL MECHANICAL CODE
2021	INTERNATIONAL PLUMBING CODE
2021	INTERNATIONAL ENERGY CODE
2021	INTERNATIONAL FIRE CODE
2023	NATIONAL ELECTRICAL CODE
2021	INTERNATIONAL ENERGY CONSERVATION CODE
OCCUPANCY CLASSIFICATION: B BUSINESS, S-1 STORAGE, A-3 ASSEMBLY	
IS THE BUILDING FULLY SPRINKLERED?	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO
IS THE BUILDING FULLY DETECTED?	<input type="checkbox"/> YES <input checked="" type="checkbox"/> NO

DATE: JULY 26, 2024
SCALE: NONE
DESIGN BY: CPB
DRAWN BY: EKE
APPROVED BY: SG
PROJ. NO.: 21098

RED ROCKS COMMUNITY COLLEGE
GENERATOR ADDITION
13300 W. 6TH AVE., LAKEWOOD, CO 80228
COVER SHEET

SHT. NO.
G00
REVISION
1

Denver // Phoenix
12600 West Colfax Avenue
Suite A-400
Lakewood, Colorado 80215
Phone 303-239-0909
www.rmhgroup.com © 2024
making a difference through engineeringsm

RMH GROUP
Mechanical • Electrical
Industrial • Sustainability

10/20/2025
07/29/24
REV. DATE
ADD 01 - ISSUED FOR BID
ISSUED FOR CONSTRUCTION
DESCRIPTION

Created on 5/6/2024
The file is a drawing
Saved by M. Manns
Plotted on 7/25/2024
Generator Plot PLANS.ctb (NOTES.dwg)

MARTIN/MARTIN, INC. GENERAL NOTES:

IN ADDITION TO THE CITY OF LAKEWOOD STANDARD NOTES, THE FOLLOWING SHALL APPLY:

- ALL MATERIALS AND CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE CURRENT CITY OF LAKEWOOD STANDARDS AND SPECIFICATIONS. STREETS, WATER MAINS, STORM SEWER AND SANITARY SEWER CONSTRUCTION SHALL BE SUBJECT TO CITY OF LAKEWOOD INSPECTION.
- THE CONTRACTOR SHALL HAVE ONE [1] SIGNED COPY OF PLANS APPROVED BY THE CITY OF LAKEWOOD AND ONE COPY OF THE APPROPRIATE DESIGN AND CONSTRUCTION STANDARDS AND SPECIFICATIONS ON THE JOB SITE AT ALL TIMES.
- CONTRACTOR SHALL NOTIFY THE ENGINEER, OWNER AND THE CITY OF LAKEWOOD [48]-HOURS PRIOR TO THE START OF CONSTRUCTION. PRE-CONSTRUCTION MEETING SHALL BE SCHEDULED WITH THE CITY OF LAKEWOOD ENGINEERING INSPECTOR [24]-HOURS PRIOR TO START OF WORK.
- THE CONTRACTOR SHALL BE SOLELY AND COMPLETELY RESPONSIBLE FOR CONDITIONS AT AND ADJACENT TO THE JOB SITE INCLUDING, BUT NOT LIMITED TO, SAFETY OF ALL PERSONS AND PROPERTY DURING PERFORMANCE OF THE WORK, TRENCH EXCAVATION AND SHORING, TRAFFIC CONTROL AND SECURITY. THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS.
- THE CITY OF LAKEWOOD/OWNER/ENGINEER CONSTRUCTION REVIEW OF THE CONTRACTOR'S PERFORMANCE IS NOT INTENDED TO INCLUDE REVIEW OF THE ADEQUACY OF THE CONTRACTOR'S SAFETY MEASURES IN, ON OR NEAR THE CONSTRUCTION SITE.
- ALL TRENCHES SHALL BE ADEQUATELY SUPPORTED AND THE SAFETY OF WORKERS PROVIDED FOR AS REQUIRED BY THE MOST RECENT OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION [OSHA] "SAFETY AND HEALTH REGULATIONS FOR CONSTRUCTION." THESE REGULATIONS ARE DESCRIBED IN SUBPART P, PART 1926 OF THE CODE OF FEDERAL REGULATIONS. SHEETING AND SHORING SHALL BE UTILIZED WHERE NECESSARY TO PREVENT ANY EXCESSIVE WIDENING OR SLOUGHING OF THE TRENCH WHICH MAY BE DETRIMENTAL TO HUMAN SAFETY, TO THE PIPE BEING PLACED OR TO ANY EXISTING SITE IMPROVEMENTS OR STRUCTURES. THE CONTRACTOR MAY BE REQUIRED TO USE AN APPROVED PILING INSTEAD OF SHEETING AND SHORING.
- CONTRACTOR SHALL OBTAIN ALL PERMITS FOR STREET CUTS, UTILITY INTERRUPTIONS AND TRAFFIC CONTROL.
- AT LEAST FIVE [5] WORKING DAYS PRIOR TO THE BEGINNING OF CONSTRUCTION, A TRAFFIC CONTROL PLAN SHALL BE SUBMITTED TO CITY OF LAKEWOOD. THE TRAFFIC CONTROL PLAN SHALL BE PREPARED BY A CERTIFIED TRAFFIC CONTROL SUPERVISOR AND SHALL BE IN CONFORMANCE WITH THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES AND WORK SHALL BEGIN UNTIL ALL TRAFFIC CONTROL DEVICES HAVE BEEN PLACED IN ACCORDANCE WITH THE PLAN. THE CONTRACTOR SHALL CONTINUOUSLY MAINTAIN THE TRAFFIC CONTROL DEVICES FOR THE ENTIRE DURATION OF THE PROJECT OR UNTIL THE ROADWAY HAS BEEN OPENED AND THE PERMANENT TRAFFIC CONTROL DEVICES HAVE BEEN INSTALLED.
- ALL TRENCH BACKFILL AND SUBGRADE PREPARATION SHALL BE TESTED TO ENSURE COMPLIANCE WITH CITY OF LAKEWOOD STANDARDS AND SHALL BE TESTED AT CITY OF LAKEWOOD REQUIRED FREQUENCIES BY A CITY OF LAKEWOOD APPROVED PRIVATE SOILS TESTING FIRM. TEST RESULTS SHALL BE SUBMITTED TO REVIEWED AND APPROVED BY THE CITY OF LAKEWOOD ENGINEERING DIVISION PRIOR TO INSTALLING BASE COURSE, ASPHALT OR CONCRETE ON PREPARED SUBGRADE. ALL BASE COURSE DENSITY SHALL ALSO BE TESTED BY THE PRIVATE SOILS FIRM AT CITY OF LAKEWOOD REQUIRED FREQUENCIES TO ENSURE COMPLIANCE WITH CITY OF LAKEWOOD REQUIREMENTS. ALL TEST RESULTS SHALL ALSO BE SUBMITTED TO THE CITY OF LAKEWOOD ENGINEERING DIVISION PRIOR TO INSTALLING PAVEMENT. ALL CONCRETE AND ASPHALT PLACED SHALL BE TESTED IN ACCORDANCE WITH CITY OF LAKEWOOD MINIMUM MATERIALS TESTING STANDARDS. TEST RESULTS SHALL BE REVIEWED AND APPROVED BY THE CITY OF LAKEWOOD ENGINEERING DIVISION PRIOR TO INITIATION OF THE REQUIRED [2] YEAR WARRANTY PERIOD.
- CONTRACTOR SHALL CONFORM TO ALL FEDERAL, STATE AND LOCAL HEALTH AND SAFETY RULES AND REGULATIONS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING ALL UTILITIES DURING CONSTRUCTION AND FOR COORDINATING WITH THE APPROPRIATE UTILITY COMPANY FOR ANY UTILITY CROSSINGS REQUIRED. REPAIR OF DAMAGED UTILITIES SHALL BE AT THE CONTRACTORS EXPENSE, INCLUDING BUT NOT LIMITED TO UNKNOWN UNDERGROUND UTILITIES.
- EXISTING FENCES, TREES, SIDEWALKS, CURBS AND GUTTERS, LANDSCAPING, STRUCTURES, AND IMPROVEMENTS DESTROYED, DAMAGED OR REMOVED DUE TO CONSTRUCTION OF THIS PROJECT SHALL BE REPLACED OR RESTORED IN LIKE KIND AT THE CONTRACTOR'S EXPENSE, UNLESS OTHERWISE INDICATED ON THESE PLANS.
- THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR MAINTAINING REASONABLE ACCESS TO AND FROM ALL OF THE ADJACENT PROPERTIES THROUGHOUT THE COURSE OF THE WORK. THE CONTRACTOR SHALL BE REQUIRED TO MEET (INDIVIDUALLY OR COLLECTIVELY) WITH ALL ADJACENT PROPERTY OWNERS WHO'S DRIVEWAY ACCESS WILL BE AFFECTED BY THE WORK, AS CONSTRUCTION CONDITIONS CHANGE AND THE WORK PROGRESSES, THE CONTRACTOR SHALL BE REQUIRED TO PERIODICALLY UPDATE THOSE PROPERTY OWNERS SO THAT THEY ARE KEPT INFORMED ABOUT THEIR ACCESS.
- OWNER/DEVELOPER SHALL OBTAIN A STORMWATER CONSTRUCTION PERMIT FROM THE COLORADO DEPARTMENT OF PUBLIC HEALTH AND ENVIRONMENT, WATER QUALITY CONTROL DIVISION, PRIOR TO CLEARING, GRADING, OR EXCAVATING A SITE OF ONE-HALF ACRE OR MORE, OR LESS THAN ONE-HALF ACRE AND PART OF A LARGER DEVELOPMENT. A COPY OF THE APPROVED PERMIT MUST BE SUBMITTED TO THE CITY OF LAKEWOOD ENGINEERING DIVISION PRIOR TO THE START OF CLEARING, GRADING OR EXCAVATING OF THE SITE. A COPY OF THE APPROVED PERMIT MUST ALSO BE AVAILABLE ON THE PROJECT SITE AT ALL TIMES DURING CONSTRUCTION.
- CONTRACTOR SHALL OBTAIN A COLORADO STATE CONSTRUCTION DEWATERING DISCHARGE PERMIT FROM THE COLORADO DEPARTMENT OF PUBLIC HEALTH AND ENVIRONMENT FOR ALL AREAS WHERE DEWATERING IS REQUIRED FROM AN EXCAVATION AND WATER IS DISCHARGED INTO A STORM SEWER, CHANNEL, IRRIGATION DITCH OR ANY WATERS OF THE UNITED STATES. A COPY OF THE APPROVED PERMIT MUST BE SUBMITTED TO THE CITY OF LAKEWOOD ENGINEERING DIVISION PRIOR TO THE START OF ANY DEWATERING. A COPY OF THE APPROVED PERMIT MUST ALSO BE AVAILABLE ON THE PROJECT SITE AT ALL TIMES DURING CONSTRUCTION.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING STORM RUNOFF AND ANY GROUNDWATER ENCOUNTERED DURING THE CONSTRUCTION OF ANY PORTION OF THIS PROJECT. GROUNDWATER SHALL BE PUMPED, PIPED, REMOVED AND DISPOSED OF IN A MANNER WHICH DOES NOT CAUSE FLOODING OF EXISTING STREETS NOR EROSION ON ADJUTING PROPERTIES IN ORDER TO CONSTRUCT THE IMPROVEMENTS SHOWN ON THESE PLANS. NO CONCRETE SHALL BE PLACED WHERE GROUNDWATER IS VISIBLE OR UNTIL THE GROUNDWATER TABLE HAS BEEN LOWERED BELOW THE PROPOSED IMPROVEMENTS. ANY UNSTABLE AREAS, AS A RESULT OF GROUNDWATER, ENCOUNTERED DURING THE CONSTRUCTION OF THE PROPOSED IMPROVEMENTS SHALL BE STABILIZED AS AGREED UPON BY THE CONTRACTOR, THE CITY OF LAKEWOOD, AND THE GEOTECHNICAL ENGINEER AT THE TIME OF OCCURENCE.
- THE CONTRACTOR IS RESPONSIBLE FOR FIELD LOCATING AND VERIFYING ELEVATIONS OF ALL EXISTING SEWER MAINS, WATER MAINS, CURBS, GUTTERS AND OTHER UTILITIES. THE POINTS OF CONNECTION SHOWN ON THE PLANS, AND AT ANY UTILITY CROSSINGS PRIOR TO INSTALLING ANY OF THE NEW IMPROVEMENTS. IF A CONFLICT EXISTS AND/OR A DESIGN MODIFICATION IS REQUIRED, THE CONTRACTOR SHALL COORDINATE WITH THE ENGINEER TO MODIFY THE DESIGN.
- PRIOR TO THE COMMENCEMENT OF ANY CONSTRUCTION, THE CONTRACTOR SHALL CONTACT ALL UTILITIES TO COORDINATE SCHEDULES.
- CONTRACTOR SHALL NOTIFY ALL BUSINESSES/RESIDENTS IN WRITING 48 HOURS PRIOR TO ANY SHUT-OFF IN SERVICE. THE NOTICES MUST HAVE CONTRACTOR'S PHONE NUMBER AND NAME OF CONTACT PERSON, AND EMERGENCY PHONE NUMBER FOR AFTER HOURS CALLS. ALL SHUT OFFS MUST BE APPROVED BY THE CITY OF LAKEWOOD UTILITY DIVISION, AND CITY OF LAKEWOOD VALVES AND APPURTENANCES SHALL BE OPERATED BY CITY OF LAKEWOOD PERSONNEL, UNLESS WRITTEN PERMISSION IS GIVEN OTHERWISE.
- ALL PUBLIC IMPROVEMENT WORK, INCLUDING CORRECTION WORK, SHALL BE INSPECTED BY A CITY OF LAKEWOOD REPRESENTATIVE WHO SHALL HAVE THE AUTHORITY TO HALT CONSTRUCTION WHEN STANDARD CONSTRUCTION PRACTICES ARE NOT BEING ADHERED TO. THE CITY OF LAKEWOOD RESERVES THE RIGHT TO ACCEPT OR REJECT ANY SUCH MATERIALS AND WORKMANSHIP THAT DOES NOT CONFORM TO ITS ENGINEERING CODE OF STANDARDS AND SPECIFICATIONS FOR THE DESIGN AND CONSTRUCTION OF PUBLIC IMPROVEMENTS. CONTRACTOR IS RESPONSIBLE FOR BEING AWARE OF, NOTIFYING, COORDINATING AND SCHEDULING ALL INSPECTIONS REQUIRED FOR FINAL APPROVALS AND PROJECT ACCEPTANCE.
- THE CONTRACTOR SHALL NOT OPERATE ANY CONSTRUCTION VEHICLES NOR PERFORM ANY CONSTRUCTION OPERATIONS BEFORE 7 AM OR AFTER 6 PM, MONDAY THROUGH FRIDAY OR BEFORE 8 AM AND AFTER 5 PM ON SATURDAYS. NO WORK WILL BE ALLOWED ON SUNDAYS OR HOLIDAYS. THE CITY OF LAKEWOOD RESERVES THE RIGHT TO FURTHER RESTRICT OR MODIFY THESE HOURS OF OPERATION IF CONDITIONS WARRANT.
- COMPACTION OF ALL TRENCHES MUST BE ATTAINED AND COMPACTION TEST RESULTS SUBMITTED TO THE ENGINEER AND THE CITY OF LAKEWOOD PRIOR TO FINAL ACCEPTANCE.
- RECORD DRAWINGS SHOWING ALL CHANGES FROM THE APPROVED CONSTRUCTION DRAWINGS SHALL BE SUBMITTED TO THE ENGINEER AND OWNER PRIOR TO INITIATION OF THE REQUIRED TWO-YEAR WARRANTY PERIOD. THE RECORD DRAWINGS WILL CONSIST OF A MARKED-UP SET OF "ISSUED FOR CONSTRUCTION" DRAWINGS VERIFYING THE FOLLOWING:
 - ALL LENGTHS, SIZES, AND MATERIALS OF INSTALLED PIPE, MANHOLES, AND ANY OTHER IMPROVEMENT.
 - HORIZONTAL LOCATIONS EITHER BY STATION AND OFFSET, OR BY NOTHING AND EXISTING COORDINATES OF ALL MANHOLES, BENDS, CLEANOUTS, VALVES, TAPS, WYES, STUBS, PLUGS, TEES, ETC.
 - ELEVATIONS AT TOP AND BOTTOM OF CONCRETE PAD.
 - ANY OTHER VARIATIONS FROM THE CONSTRUCTION DOCUMENTS MUST BE CLEARLY NOTED AND DETAILED ON THE PLANS.
 - AS-BUILT FIELD NOTES, FROM WHICH THE AS-BUILT DRAWINGS ARE PREPARED, ARE TO BE PROVIDED AND STAMPED/SIGNED AND DATED BY A COLORADO REGISTERED PROFESSIONAL LAND SURVEYOR.
- THE CONTRACTOR SHALL WARRANT ALL WORK TO BE FREE FROM DEFECTS IN WORKMANSHIP AND MATERIALS FOR A PERIOD OF TWO-YEARS FROM THE DATE OF ACCEPTANCE INTO THE WARRANTY PERIOD OF ALL CONSTRUCTION CALLED FOR BY THE PUBLIC IMPROVEMENTS AGREEMENT WITH THE CITY OF LAKEWOOD.
- DURING CONSTRUCTION AND UPON COMPLETION OF CONSTRUCTION, THE SITE SHALL BE CLEANED AND RESTORED TO A CONDITION EQUAL TO, OR BETTER THAN, THAT WHICH EXISTED BEFORE CONSTRUCTION.
- THE OWNER/DEVELOPER AND/OR THEIR ASSIGNS IS HEREBY NOTIFIED THAT IT IS TYPICAL AND LIKELY THAT SOME MOVEMENT OF THE SURFACE GRADES WILL OCCUR OVER TIME DUE TO VARIOUS FACTORS THAT ARE NOT IN CONTROL OF THE DESIGNERS. THUS, A ROUTINE AND DILIGENT MAINTENANCE PROGRAM IS REQUIRED TO MAINTAIN THE PROPER GRADING AND DRAINAGE THROUGHOUT THE PROJECT.

GRADING NOTES:

- ALL SITE GRADING [EXCAVATION, EMBANKMENT, AND COMPACTION] SHALL CONFORM TO THE PROJECT SPECIFICATIONS AND SHALL FURTHER BE IN CONFORMANCE WITH THE CITY OF LAKEWOOD'S "STANDARDS AND SPECIFICATIONS FOR THE DESIGN AND CONSTRUCTION OF PUBLIC IMPROVEMENTS," LATEST EDITION.
- ALL NEWLY CONSTRUCTED OR ALTERATIONS OF ACCESSIBILITY ROUTES (WALKS, RAMPS, ENTRANCES, ETC.) SHALL COMPLY WITH THE RULES AND REGULATIONS SET FORTH BY ADA, ADAAG, CITY, STATE, FEDERAL OR JURISDICTION HAVING AUTHORITY, INCLUDING BUT NOT LIMITED TO: 5% MAXIMUM GRADE ON WALKS WITHOUT HANDRAILS, 8.33% MAXIMUM GRADE ON WALKS WITH HANDRAILS AND LEVEL LANDINGS (MAXIMUM 2% COMPOSITE SLOPE), 2% MAXIMUM CROSS SLOPE ON WALKS AND 2% MAXIMUM COMPOSITE SLOPE IN ACCESSIBLE PARKING/LOADING AREAS. NO TOLERANCE REGARDING MAXIMUM SLOPES WILL BE ALLOWED. DURING CONSTRUCTION, CONTRACTOR SHALL COORDINATE AS NECESSARY WITH OWNER, DEVELOPER, ENGINEER, ARCHITECT, OR DESIGNATED OFFICIAL IF RULES AND REGULATIONS OF ACCESSIBILITY ROUTES CAN NOT BE MET. IN ADDITION, OWNER IS ADVISED THAT REGULAR MAINTENANCE PROGRAMS SHOULD BE IMPLEMENTED AFTER CONSTRUCTION TO KEEP EXISTING ROUTES SAFE, USABLE, AND ADA COMPLIANT.
- EXISTING ELEVATIONS SHOWN ON THIS DRAWING HAVE BEEN DEPICTED FROM BEST AVAILABLE INFORMATION AND ARE SHOWN TO THE EXTENT KNOWN. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO FIELD VERIFY EXISTING GRADE CONDITIONS AT THE LIMITS OF CONSTRUCTION AND AT LOCATIONS THAT INTERFACE WITH EXISTING OR PROPOSED STRUCTURES AND NOTIFY THE ENGINEER OF ANY DISCREPANCIES THAT CONTRADICT THE ENGINEERS INTENT FOR DRAINAGE PATTERNS, MAXIMUM AND MINIMUM SLOPES, AND PROPOSED ELEVATIONS AS SHOWN ON THE PLAN. THE ENGINEER WILL NOT BE LIABLE FOR ANY COSTS ASSOCIATED WITH CHANGES TO THE DESIGN WITHOUT PROPER NOTIFICATION.
- PROPOSED CONTOURS AND SPOT ELEVATIONS AS SHOWN HEREIN ARE DEFINED AS FINISHED ELEVATION AFTER PAVING, LANDSCAPING, ETC. CONTRACTOR SHALL COORDINATE WITH GEOTECH FOR PAVEMENT THICKNESS AND LANDSCAPE FOR THICKNESS OF TOPSOIL, SOD AND LANDSCAPE MATERIALS.

ALL SPOTS ARE TO FLOWLINE UNLESS OTHERWISE NOTED. FG = FINISHED GRADE, FF = FINISH FLOOR, TOF = TOP OF FOUNDATION, HP = HIGH POINT, LP = LOW POINT, TOW = TOP OF WALL [FINISHED GRADE AT BACK OF WALL], BOW = BOTTOM OF WALL [FINISHED GRADE AT FACE OF WALL], GB = GRADE BREAK, FL = FLOWLINE, TOC = TOP OF CURB.
- TEMPORARY CUT/FILL SLOPES SHALL NOT EXCEED A STEEPNESS OF [1:1] (H:V). PERMANENT SLOPES SHALL NOT EXCEED [4:1] (H:V) [UNLESS NOTED OTHERWISE] IN AREAS TO BE SEEDED OR SODDED.
- CONTRACTOR SHALL ADJUST ALL EXISTING AND PROPOSED MANHOLE RIMS, VALVE BOXES, ETC. TO MATCH FINAL GRADE.

DEMOLITION NOTES:

- CONTRACTOR SHALL CLEAR AND GRUB EXISTING VEGETATION PRIOR TO CONSTRUCTION. COORDINATE MATERIAL DISPOSAL WITH OWNER'S REPRESENTATIVE.
- CONTRACTOR SHALL PRESERVE EXISTING VEGETATION OUTSIDE OF THE PROJECT LIMITS.
- BARRIERS/FENCING SHALL BE PROVIDED PRIOR TO SITE DEMOLITION TO PROVIDE FOR THE SAFETY OF WORKERS AND PASSERSBY. THE CONTRACTOR SHALL PROVIDE A BARRIER/FENCING PLAN TO FACILITIES MANAGEMENT FOR APPROVAL PRIOR TO CONSTRUCTION.
- G.C. SHALL PROVIDE FOR DUST CONTROL DURING DEMOLITION TO INCLUDE COVERING OF ALL TRUCKS HAULING DEBRIS OFFSITE, PERIODICALLY CLEANING AND SWEEPING ADJACENT STREETS, AND APPLYING AN APPROVED DUST PALLIATIVE AS NECESSARY.
- THOROUGHLY CLEAN ALL AREAS, SURFACES, BUILDINGS AND STRUCTURES IMPACTED BY DEMOLITION PRIOR TO START OF NEW CONSTRUCTION.
- THE ENGINEER ASSUMES NO RESPONSIBILITY FOR BURIED UTILITIES. THE G.C. IS RESPONSIBLE FOR LOCATING AND PROTECTING ALL UTILITIES NOT DESIGNATED FOR REMOVAL PRIOR TO AND DURING CONSTRUCTION.
- EXISTING CONCRETE AT DEMOLITION LIMITS SHALL BE CUT ONLY AT EXISTING JOINTS.
- ALL EXISTING MANHOLES, WATER VALVES AND EXISTING UTILITY STRUCTURES NOT DESIGNATED FOR REMOVAL SHALL BE ADJUSTED TO FINAL FINISH GRADE.
- TREES, LANDSCAPING, STRUCTURES AND UTILITIES NOT DESIGNATED FOR DEMOLITION SHALL REMAIN AND BE PROTECTED DURING CONSTRUCTION.
- CONTRACTOR SHALL COORDINATE ALL DEMOLITION ACTIVITIES WITH OWNER'S REPRESENTATIVE.
- CONTRACTOR SHALL COORDINATE WITH OWNER AND UTILITY PROVIDER FOR DEMOLITION, RELOCATION, AND NEW DRY UTILITY SERVICES (GAS, ELECTRIC, CABLE TV, FIBER OPTIC, TELEPHONE, ETC).
- CONTRACTOR SHALL COORDINATE WITH OWNER FOR SALVAGING OF EXISTING ONSITE MATERIALS (EG. LIGHT POLE, IRRIGATION VALVES, SIGNAGE, ETC.).
- ALL SITE UTILITIES NO LONGER IN SERVICE SHALL BE REMOVED OR ABANDONED PER THE UTILITY PROVIDER'S REQUIREMENTS.
- NO CONSTRUCTION ACCESS, ACTIVITY, OR STORAGE OF MATERIALS/DEBRIS/EQUIPMENT IS PERMITTED WITHIN TREE PROTECTION ZONES (TPZ), INCLUDING GRADING, INSTALLATION OF UNDERGROUND UTILITIES, INSTALLATION OF SITE IMPROVEMENTS, AND/OR GRUBBING. ALL CONSTRUCTION ACTIVITY MUST OCCUR OUTSIDE TREE PROTECTION ZONES (I.E. DRIPLINES OF TREES). REFER TO LANDSCAPE FOR TREE PROTECTION ZONE (TPZ) LIMITS AND DETAIL.

EROSION CONTROL NOTES:

- THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL REQUIRED PERMITS AND IMPLEMENTING AND MAINTAINING EROSION AND SEDIMENT CONTROL MEASURES AT ALL TIMES DURING CONSTRUCTION TO PREVENT DAMAGING FLOWS ON THE SITE AND IN THE WATERSHED BELOW THE SITE. CONTROL SYSTEMS SHALL BE INSTALLED PRIOR TO STRIPPING OF NATIVE VEGETATIVE COVER AND AS GRADING PROGRESSES. REFER TO SEDIMENT AND EROSION CONTROL PLANS AND STORM WATER MANAGEMENT PLAN. CONDITIONS IN THE FIELD MAY WARRANT EROSION CONTROL MEASURES IN ADDITION TO WHAT IS SHOWN ON THESE PLANS. THE PLAN MAY BE MODIFIED WITH APPROPRIATE APPROVALS AS FIELD CONDITIONS WARRANT.
 - NATURAL VEGETATION SHALL BE RETAINED AND PROTECTED WHEREVER POSSIBLE. EXPOSURE OF SOIL TO EROSION BY REMOVAL OR DISTURBANCE OF VEGETATION SHALL BE LIMITED TO THE AREA REQUIRED FOR IMMEDIATE CONSTRUCTION OPERATION AND FOR THE SHORTEST PRACTICAL PERIOD OF TIME.
 - TOPSOIL SHALL BE STOCKPILED TO THE EXTENT PRACTICABLE ON THE SITE FOR USE ON AREAS TO BE REVEGETATED. ANY AND ALL STOCKPILES SHALL BE LOCATED AND PROTECTED FROM EROSION ELEMENTS.
 - AT ALL TIMES, THE PROPERTY SHALL BE MAINTAINED AND/OR WATERED TO PREVENT WIND-CAUSED EROSION. EARTHWORK OPERATIONS SHALL BE DISCONTINUED WHEN FUGITIVE DUST SIGNIFICANTLY IMPACTS ADJACENT PROPERTY. IF EARTHWORK IS COMPLETE OR DISCONTINUED AND DUST FROM THE SITE CONTINUES TO CREATE PROBLEMS, THE CONTRACTOR SHALL IMMEDIATELY INSTITUTE MITIGATIVE MEASURES AND SHALL CORRECT DAMAGE TO ADJACENT PROPERTY.
 - PERMANENT OR TEMPORARY SOIL STABILIZATION MEASURES SHALL BE APPLIED TO DISTURBED AREAS WITHIN 30 DAYS AFTER FINAL GRADE IS REACHED ON ANY PORTION OF THE SITE. UNLESS SPECIFIED OTHERWISE, TEMPORARY VEGETATION SHALL BE INSTALLED ON ALL DISTURBED AREAS WHERE PERMANENT SURFACE IMPROVEMENTS ARE NOT SCHEDULED FOR INSTALLATION WITHIN THREE MONTHS. TEMPORARY VEGETATION SHALL BE A VIGOROUS, DROUGHT TOLERANT, NATIVE SPECIES MIX. PROJECT SCHEDULING SHOULD TAKE ADVANTAGE OF SPRING OR FALL PLANTING SEASONS FOR NATURAL GERMINATION, BUT SEEDED AREAS SHALL BE IRRIGATED, IF CONDITIONS MERIT. REFER TO THE LANDSCAPE PLAN FOR FINAL LANDSCAPING.
 - TEMPORARY FENCES SHALL BE INSTALLED ALONG ALL BOUNDARIES OF THE CONSTRUCTION LIMITS OR PROPERTY LINES AS SHOWN ON THE APPROVED EROSION CONTROL PLAN, TO PREVENT GRADING ON PROPERTY NOT OWNED BY THE OWNER/DEVELOPER. IN ADDITION, THE CITY OF LAKEWOOD MAY REQUIRE ADDITIONAL TEMPORARY FENCES IF FIELD CONDITIONS WARRANT.
 - THE CONTRACTOR SHALL PREVENT SEDIMENT, DEBRIS AND ALL OTHER POLLUTANTS FROM ENTERING THE STORM SEWER SYSTEM DURING ALL DEMOLITION, EXCAVATION, TRENCHING, GRADING OR OTHER CONSTRUCTION OPERATIONS THAT ARE PART OF THIS PROJECT. THE CONTRACTOR SHALL BE HOLD RESPONSIBLE FOR REMEDIATION OF ANY ADVERSE IMPACTS TO ADJACENT WATERWAYS, ROADWAYS, WETLANDS, ETC., RESULTING FROM WORK DONE AS PART OF THIS PROJECT.
 - THE CONTRACTOR AND/OR THEIR AUTHORIZED AGENTS SHALL REMOVE ALL SEDIMENT, MUD, CONSTRUCTION DEBRIS, OR OTHER POTENTIAL POLLUTANTS THAT MAY HAVE BEEN INADVERTENTLY DISCHARGED TO, OR ACCUMULATED IN, THE FLOWLINES AND PUBLIC RIGHT-OF-WAY AS A RESULT OF CONSTRUCTION ACTIVITIES ASSOCIATED WITH THIS SITE DEVELOPMENT OR CONSTRUCTION PROJECT.
 - THE GRADING CONTRACTOR AND/OR THEIR AUTHORIZED AGENTS SHALL ENSURE THAT ALL LOADS OF CUT AND FILL MATERIAL IMPORTED TO OR EXPORTED FROM THIS SITE SHALL BE PROPERLY COVERED TO PREVENT LOSS OF THE MATERIAL DURING TRANSPORT ON PUBLIC ROADWAYS.
 - APPROVED EROSION AND SEDIMENT CONTROL "BEST MANAGEMENT PRACTICES" [BMP] SHALL BE MAINTAINED AND KEPT IN GOOD REPAIR FOR THE DURATION OF THIS PROJECT. AT A MINIMUM, THE CONTRACTOR OR HIS AGENT SHALL INSPECT ALL BMPs WEEKLY AND AFTER SIGNIFICANT PRECIPITATION EVENTS. ALL NECESSARY MAINTENANCE AND REPAIR SHALL BE COMPLETED IN A TIMELY MANNER. ACCUMULATED SEDIMENT AND DEBRIS SHALL BE REMOVED FROM A BMP WHEN THE SEDIMENT LEVEL REACHES ONE HALF THE HEIGHT OF THE BMP OR, AT ANY TIME THAT SEDIMENT OR DEBRIS ADVERSELY IMPACTS THE FUNCTIONING OF THE BMP.
 - WATER USED IN THE CLEANING OF CONCRETE TRUCK DELIVERY CHUTES SHALL BE DISCHARGED INTO A PREDEFINED, BERMED CONTAINMENT AREA ON THE JOB SITE. THE REQUIRED CONTAINMENT AREA IS TO BE BERMED SO THAT WASH WATER IS TOTALLY CONTAINED. WASH WATER DISCHARGED INTO THE CONTAINMENT AREA SHALL BE ALLOWED TO INFILTRATE OR EVAPORATE. DRIED CONCRETE WASTE SHALL BE REMOVED FROM THE CONTAINMENT AREA AND PROPERLY DISPOSED OF. SHOULD A PREDEFINED BERMED CONTAINMENT AREA NOT BE AVAILABLE DUE TO THE PROJECT SIZE, OR LACK OF AN AREA WITH A SUITABLE GROUND SURFACE FOR ESTABLISHING A CONTAINMENT AREA, PROPER DISPOSAL OF READY MIX WASHOUT AND RINSE OFF WATER AT THE JOB SITE SHALL CONFORM TO THE APPROVED TECHNIQUES AND PRACTICES IDENTIFIED IN THE COLORADO DEPARTMENT OF PUBLIC HEALTH & ENVIRONMENT'S TRAINING VIDEO ENTITLED "BUILDING FOR A CLEANER ENVIRONMENT: READY MIX WASHOUT TRAINING", AND ITS ACCOMPANYING MANUAL ENTITLED, "READY MIX WASHOUT GUIDEBOOK: VEHICLE AND EQUIPMENT WASHOUT AT CONSTRUCTION SITES." THE DIRECT OR INDIRECT DISCHARGE OF WATER CONTAINING WASTE CONCRETE TO THE STORM SEWER SYSTEM IS PROHIBITED. INFORMATION ABOUT, OR COPIES OF THE VIDEO AND TRAINING MANUAL ARE AVAILABLE FROM THE WATER QUALITY CONTROL DIVISION, COLORADO DEPARTMENT OF PUBLIC HEALTH & ENVIRONMENT, 4300 CHERRY CREEK DRIVE SOUTH, DENVER, COLORADO 80222-1530, 303-692-3555.
 - THE CONTRACTOR SHALL PROTECT ALL STORM SEWER FACILITIES ADJACENT TO ANY LOCATION WHERE PAVEMENT CUTTING OPERATIONS INVOLVING WHEEL CUTTING, SAW CUTTING OR ABRASIVE WATER JET CUTTING ARE TO TAKE PLACE. THE CONTRACTOR SHALL REMOVE AND PROPERLY DISPOSE OF ALL WASTE PRODUCTS GENERATED BY SAID CUTTING OPERATIONS ON A DAILY BASIS. THE DISCHARGE OF ANY WATER CONTAMINATED BY WASTE PRODUCTS FROM CUTTING OPERATIONS TO THE STORM SEWER SYSTEM IS PROHIBITED.
 - PAVED SURFACES WHICH ARE ADJACENT TO CONSTRUCTION SITES SHALL BE SWEEPED IN A TIMELY MANNER WHEN SEDIMENT AND OTHER MATERIALS ARE TRACKED OR DISCHARGED ON TO THEM. EITHER SWEEPING BY HAND OR USE OF STREET SWEEPERS IS ACCEPTABLE. STREET SWEEPERS USING WATER WHILE SWEEPING IS PREFERRED IN ORDER TO MINIMIZE DUST. FLUSHING OFF PAVED SURFACES WITH WATER IS PROHIBITED.
- ABBREVIATIONS:

APPROX	APPROXIMATE	PT	POINT OF HORIZONTAL TANGENCY
ARCH	ARCHITECT	PCC	POINT OF COMPOUND CURVE
BLDG	BUILDING	PERF	PERFORATED
BM	BENCHMARK	PERIM	PERIMETER
BOC	BACK OF CURB	PERP	PERPENDICULAR
CIP	CAST IRON PIPE	PI	POINT OF HORIZONTAL INTERSECTION
CL	CENTERLINE	PIV	PRESSURE INDICATOR VALVE
CMF	CORRUGATED METAL PIPE	PL	PROPERTY LINE
CO	CLEANOUT	PLBG	PLUMBING
CONC	CONCRETE	POC	POINT OF CURVE
CONT	CONTOUR	POT	POINT OF TANGENT
COR	CORNER	PRC	POINT OF REVERSE CURVE
CU	COPPER	PRKG	PARKING
DEMO	DEMOLITION	PRV	PRESSURE REDUCING VALVE
DIA OR Ø	DIAMETER	PVC	POLYVINYL CHLORIDE PIPE
DIM	DIMENSION	PVI	POINT OF VERTICAL INTERSECTION
DIP	DUCTILE IRON PIPE	PVMT	PAVEMENT
DTL	DETAIL	PVT	POINT OF VERTICAL TANGENCY
EL	ELEVATION	RCP	REINFORCED CONCRETE PIPE
ELEC	ELECTRICAL	RD	ROOF DRAIN
ESMT	EASEMENT	R.O.W.	RIGHT OF WAY
EX	EXISTING	RT	RIGHT
FDC	FIRE DEPARTMENT CONNECTION	SSWR	SANITARY SEWER
FES	FLARED END SECTION	SF	SQUARE FOOT
FFE	FINISHED FLOOR ELEVATION	STA	STATION
FGW	FINISHED GRADE AT WALL	STRM	STORM SEWER
FHY	FIRE HYDRANT	STRC	STRUCTURAL
FL	FLOW LINE	SWLK	SIDEWALK
FT	FOOT	SY	SQUARE YARD
GB	GRADE BREAK	TELE	TELEPHONE
GR	GRATE (AREA OR VALLEY INLETS)	TB	THRUST BLOCK
GV	GATE VALVE	TEMP	TEMPORARY
HERCP	HORIZONTAL ELLIPTICAL REINFORCED CONCRETE PIPE	TOC	TOP OF CURB
HOPE	HIGH DENSITY POLYETHYLENE PIPE	TOW	TOP OF WALL (RE: NOTE BELOW)
HGL	HYDRAULIC GRADE LINE	TYP.	TYPICAL
HORZ	HORIZONTAL	UD	UNDER DRAIN
HP	HIGH POINT	UG	UNDERGROUND
INV	INVERT	VERT	VERTICAL
LF	LINAL FEET	VC	VERTICAL CURVE
LP	LOW POINT		
LT	LEFT		
MAX	MAXIMUM		
MECH	MECHANICAL		
MEP	MECHANICAL, ELECTRICAL AND PLUMBING		
MH	MANHOLE		
MIN	MINIMUM		
N.I.C.	NOT IN CONTRACT		
NTS	NOT TO SCALE		

NOTE: TOW SHALL BE TOP OF WATER ON UTILITY SHEETS ONLY AND TOP OF WALL ON ALL OTHER SHEETS.



VICINITY MAP
SCALE: 1"=1000'

SHEET LIST TABLE	
SHEET NUMBER	SHEET TITLE
C1.0	NOTES
C1.1	EXISTING CONDITIONS PLAN
C1.2	GRADING AND EROSION CONTROL PLAN
C1.3	EROSION CONTROL DETAILS
C1.4	EROSION CONTROL DETAILS

RED ROCKS COMMUNITY COLLEGE
GENERATOR ADDITION

RMH GROUP

CONSULTING ENGINEERS

Denver // Phoenix
12600 West Colfax Avenue
Suite A-400
Lakewood, Colorado 80215
Phone 303-239-0809
www.rmhgroup.com © 2024

MARTIN/MARTIN, INC.

CONSULTING ENGINEERS

Denver
12400 West Colfax Avenue
Suite 100
Lakewood, Colorado 80215
303-637-6500
martinmartin.com


NOTES

BID DOCUMENTS

ISSUED FOR CONSTRUCTION
DATE 07/26/24
REV.

SHT. NO.	REVISION
C1.0	0

Created on 5/10/2024
File Path: \\mimms\projects\24\1408-REC - Generator Pad\PLANS\CD\1408-151A-00.dwg - DEW.dwg
User: mmmms
Plotted on 7/25/2024



BASIS OF BEARINGS

BEARINGS ARE BASED ON THE NORTH LINE OF THE NORTHEAST QUARTER OF SECTION 7, TOWNSHIP 4 SOUTH, RANGE 69 WEST OF THE SIXTH PRINCIPAL MERIDIAN ASSUMED TO BEAR N89°55'10"E AND BEING MONUMENTED BY A FOUND 3-1/4" ALUMINUM CAP IN RANGE BOX PLS#19591 AT THE NORTH QUARTER CORNER AND A FOUND 2" ALUMINUM CAP PLS #14112 AT THE NORTHEAST CORNER.

BENCHMARK

ELEVATIONS ARE BASED ON THE CITY OF LAKEWOOD AND COUNTY OF JEFFERSON BM #NGS-151 A CHISELED SQUARE ON THE CURB, SOUTHEAST CORNER OF WEST 6TH AVENUE AND WRIGHT STREET, MIDWAY BETWEEN THE ADA RAMP AND THE STORM INLET.

ELEVATION = 5788.39' (NGVD1929) DATUM.

UTILITY NOTE



UTILITIES DEPICTED HEREON, DO NOT COMPLY WITH ASCE 38 UTILITY LOCATE STANDARD QUALITY LEVEL A OR B, UNLESS A SEPARATE PLAN SHEET ENTITLED "ASCE 38 UTILITY QUALITY LEVEL B PLAN (A&B)", STAMPED BY A COLORADO PE, IS INCLUDED IN THE PLAN SET. THE UTILITY LOCATES SHOWN HEREON REPRESENT ASCE QUALITY LEVEL D, THUS THE CONTRACTOR IS REQUIRED TO VERIFY THE ACTUAL LOCATION OF ALL UTILITIES PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL COMPLY WITH ALL THE PROVISIONS OF SENATE BILL 18-167 THAT REQUIRE NOTIFICATION OF THE NOTIFICATION ASSOCIATION AND COMPLIANCE WITH CURRENT 811 PROGRAM REQUIREMENTS.

FOR UNDERGROUND UTILITIES MARTIN / MARTIN INC. RELIED UPON LOCATIONS AND MARKINGS PROVIDED BY UNDERGROUND CONSULTING SOLUTIONS.

NOTE:

- EXISTING PHONE LINE RUNS FROM THE GAS HOUSE TO THE MAIN BUILDING. LOCATION IS UNKNOWN AND CONTRACTOR TO FIELD VERIFY PRIOR TO PAD CONSTRUCTION IN ORDER TO CONFIRM THERE IS NO CONFLICT. CONTACT ENGINEER WITH ANY ISSUES.

LEGEND	
	PROPERTY LINE
	RIGHT-OF-WAY LINE
	SECTION LINE
	EASEMENT
	RETAINING WALL
	CURB & GUTTER
	CONTOURS
	STORM SEWER
	ROOF DRAIN
	STORM MANHOLE
	STORM INLET
	FLARED END SECTION
	SANITARY SEWER
	SANITARY MANHOLE
	CLEAN OUT
	WATER LINE
	WATER VALVE
	FIRE HYDRANT
	WATER METER
	IRRIGATION CONTROL
	OVERHEAD ELECTRIC
	ELECTRIC LINE
	LIGHT POLE
	POWER POLE
	ELECTRIC METER
	TELEPHONE LINE
	TELEPHONE PEDESTAL
	CABLE TV
	GAS LINE
	MONITOR WELL
	SIGN
	DECIDUOUS TREE
	EVERGREEN TREE
	BUSH/SHRUB
	HANDICAP RAMPS
	DESCRIPTIONS



CALL 811 2-BUSINESS DAYS IN ADVANCE BEFORE YOU DIG, GRADE OR EXCAVATE FOR MARKING OF UNDERGROUND MEMBER UTILITIES

MARTIN/MARTIN ASSUMES NO RESPONSIBILITY FOR UTILITY LOCATIONS, UNLESS OTHERWISE NOTED, THE UTILITIES SHOWN ON THIS DRAWING ARE BASED ON INFORMATION PROVIDED BY OTHERS AND DEPICTED AS ASCE (38) QUALITY LEVEL D, IN ACCORDANCE WITH THE PROVISIONS OF COLORADO REVISED STATUTE, TITLE 9, IT IS THE CONTRACTORS RESPONSIBILITY TO CALL COLORADO 811 UTILITY LOCATE SERVICE FOR UTILITY LOCATES BEFORE DIGGING, AND FIELD VERIFY THE SIZE, MATERIAL, HORIZONTAL AND VERTICAL LOCATION OF ALL EXISTING UTILITIES (DEPICTED OR NOT DEPICTED) PRIOR TO THE COMMENCEMENT OF ANY CONSTRUCTION.

**RED ROCKS COMMUNITY COLLEGE
GENERATOR ADDITION**

RMH GROUP
Denver // Phoenix
12600 West Colfax Avenue
Suite A-400
Lakewood, Colorado 80215
Phone 303-239-0809
www.rmhgroup.com © 2024


MARTIN/MARTIN CONSULTING ENGINEERS
Lakewood, Colorado 80215
303.651.1500
martinmartin.com

**Mechanical • Electrical
Industrial • Sustainability**
making a difference through engineeringSM

EXISTING CONDITIONS PLAN
BID DOCUMENTS

DATE: JULY 26, 2024	SCALE: AS NOTED	DESIGN BY: M. LIBERATI	DRAWN BY: M. MARNS	APPROVED BY: M. THORNBROUGH	PROJ. NO.: 24-0008
SHT. NO.	C1.1				REVISION
					0


REV.	DATE	ISSUED FOR	CONSTRUCTION	DESCRIPTION
	07/26/24			



CALL 811 2-BUSINESS DAYS IN ADVANCE
BEFORE YOU DIG, GRADE OR EXCAVATE FOR
MARKING OF UNDERGROUND MEMBER UTILITIES

MARTIN/MARTIN ASSUMES NO RESPONSIBILITY FOR UTILITY
LOCATIONS UNLESS OTHERWISE NOTED. THE UTILITIES SHOWN ON
THIS DRAWING ARE BASED ON INFORMATION PROVIDED BY OTHERS
AND DEPICTED AS ASCE (38) QUALITY LEVEL D, IN ACCORDANCE
WITH THE PROVISIONS OF COLORADO REVISED STATUTE, TITLE 9,
§ 9-2-101. THE CONTRACTORS RESPONSIBILITY TO CALL COLORADO 8
UTILITY LOCATE SERVICE FOR UTILITY LOCATES BEFORE DIGGING
IN THIS FIELD OF WORK IS NOT DELETED BY THE VERTICAL
LOCATION OF ALL EXISTING UTILITIES (DEPICTED OR NOT DEPICTED
PRIOR TO THE COMMENCEMENT OF ANY CONSTRUCTION.


Sediment Control Log (SCL) SC-2



SCL-1. TRENCHED SEDIMENT CONTROL LOG

November 2015 Urban Drainage and Flood Control District Urban Storm Drainage Criteria Manual Volume 3 SCL-3


Stabilized Staging Area (SSA) SM-6



SSA-1. STABILIZED STAGING AREA

November 2010 Urban Drainage and Flood Control District Urban Storm Drainage Criteria Manual Volume 3 SSA-3

Sediment Control Log (SCL) SC-2



SCL-2. COMPOST SEDIMENT CONTROL LOG (WEIGHTED)

SCL-4 Urban Drainage and Flood Control District Urban Storm Drainage Criteria Manual Volume 3 November 2015

Stabilized Staging Area (SSA) SM-6

STABILIZED STAGING AREA MAINTENANCE NOTES

5. STABILIZED STAGING AREA SHALL BE ENLARGED IF NECESSARY TO CONTAIN PARKING, STORAGE, AND UNLOADING/LOADING OPERATIONS.

6. THE STABILIZED STAGING AREA SHALL BE REMOVED AT THE END OF CONSTRUCTION. THE GRANULAR MATERIAL SHALL BE REMOVED OR, IF APPROVED BY THE LOCAL JURISDICTION, USED ON SITE. AND THE AREA COVERED WITH TOPSOIL, SEEDED AND MULCHED OR OTHERWISE STABILIZED IN A MANNER APPROVED BY LOCAL JURISDICTION.


NOTE: MANY MUNICIPALITIES PROHIBIT THE USE OF RECYCLED CONCRETE AS GRANULAR MATERIAL FOR STABILIZED STAGING AREAS DUE TO DIFFICULTIES WITH RE-ESTABLISHMENT OF VEGETATION IN AREAS WHERE RECYCLED CONCRETE WAS PLACED.

NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

(DETAILS ADAPTED FROM DOUGLAS COUNTY, COLORADO, NOT AVAILABLE IN AUTOCAD)

SSA-4 Urban Drainage and Flood Control District Urban Storm Drainage Criteria Manual Volume 3 November 2010


Sediment Control Log (SCL) SC-2



SCL-3. SEDIMENT CONTROL LOGS TO CONTROL SLOPE LENGTH

November 2015 Urban Drainage and Flood Control District Urban Storm Drainage Criteria Manual Volume 3 SCL-5

Inlet Protection (IP) SC-6



IP-1. BLOCK AND ROCK SOCK SUMP OR ON GRADE INLET PROTECTION

BLOCK AND CURB SOCK INLET PROTECTION INSTALLATION NOTES

1. SEE ROCK SOCK DESIGN DETAIL FOR INSTALLATION REQUIREMENTS.

2. CONCRETE "CINDER" BLOCKS SHALL BE LAID ON THEIR SIDES AROUND THE INLET IN A SINGLE ROW, ABUTTING ONE ANOTHER WITH THE OPEN END FACING AWAY FROM THE CURB.

3. GRAVEL BAGS SHALL BE PLACED AROUND CONCRETE BLOCKS, CLOSELY ABUTTING ONE ANOTHER AND JOINED TOGETHER IN ACCORDANCE WITH ROCK SOCK DESIGN DETAIL.

MINIMUM OF TWO CURB SOCKS APPROX 30 DEG. BLOCK AND ROCK SOCK INLET PROTECTION(SEE DETAIL IP-1)

CURB SOCK

FLOW

5'-5' TYP.

5' MIN.

IP-2. CURB ROCK SOCKS UPSTREAM OF INLET PROTECTION

CURB ROCK SOCK INLET PROTECTION INSTALLATION NOTES

1. SEE ROCK SOCK DESIGN DETAIL INSTALLATION REQUIREMENTS.

2. PLACEMENT OF THE SOCK SHALL BE APPROXIMATELY 30 DEGREES FROM PERPENDICULAR IN THE OPPOSITE DIRECTION OF FLOW.

3. SOCKS ARE TO BE FLUSH WITH THE CURB AND SPACED A MINIMUM OF 5 FEET APART.

4. AT LEAST TWO CURB SOCKS IN SERIES ARE REQUIRED UPSTREAM OF ON-GRADE INLETS.


IP-4 Urban Drainage and Flood Control District Urban Storm Drainage Criteria Manual Volume 3 August 2013

Sediment Control Log (SCL) SC-2



SC-6 Urban Drainage and Flood Control District Urban Storm Drainage Criteria Manual Volume 3 November 2015

Inlet Protection (IP) SC-6



IP-3. ROCK SOCK SUMP/AREA INLET PROTECTION

ROCK SOCK SUMP/AREA INLET PROTECTION INSTALLATION NOTES

1. SEE ROCK SOCK DESIGN DETAIL FOR INSTALLATION REQUIREMENTS.

2. STRAW WATLES/SEDIMENT CONTROL LOGS MAY BE USED IN PLACE OF ROCK SOCKS FOR INLETS IN PERVIOUS AREAS. INSTALL PER SEDIMENT CONTROL LOG DETAIL.

MINIMUM OF TWO CURB SOCKS APPROX 30 DEG. BLOCK AND ROCK SOCK INLET PROTECTION(SEE DETAIL IP-1)

CURB SOCK

FLOW

5'-5' TYP.

5' MIN.

IP-2. CURB ROCK SOCKS UPSTREAM OF INLET PROTECTION

CURB ROCK SOCK INLET PROTECTION INSTALLATION NOTES

1. SEE ROCK SOCK DESIGN DETAIL INSTALLATION REQUIREMENTS.

2. PLACEMENT OF THE SOCK SHALL BE APPROXIMATELY 30 DEGREES FROM PERPENDICULAR IN THE OPPOSITE DIRECTION OF FLOW.

3. SOCKS ARE TO BE FLUSH WITH THE CURB AND SPACED A MINIMUM OF 5 FEET APART.

4. AT LEAST TWO CURB SOCKS IN SERIES ARE REQUIRED UPSTREAM OF ON-GRADE INLETS.

August 2013 Urban Drainage and Flood Control District Urban Storm Drainage Criteria Manual Volume 3 IP-5

RED ROCKS COMMUNITY COLLEGE GENERATOR ADDITION

DATE: JULY 26, 2024	SCALE: AS NOTED	DESIGN BY: M. LIBERATI	DRAWN BY: M. MARKS	APPROVED BY: M. THORNBROUGH	PROJ. NO.: 24-0008
SHT. NO.	C1.3	REVISION	0		

RMH GROUP
12600 West Colfax Avenue
Suite A-400
Lakewood, Colorado 80215
Phone 303-239-0909
www.rmhgroup.com © 2024

making a difference through engineeringSM

Mechanical • Electrical
Industrial • Sustainability


MARTIN/MARTIN CONSULTING ENGINEERS
12489 West Colfax Avenue
Lakewood, Colorado 80215
303.657.1500
martinmartin.com

EROSION CONTROL DETAILS
BID DOCUMENTS

ISSUED FOR CONSTRUCTION
REV. DATE
07/26/24

Created on 5/10/2024
File Path: C:\Users\mimmons\OneDrive\Documents\RedRocks\Generator\Plans\CDs\EROSION DETAILS.dwg
Sheet Name: Erosion Details
Plotted on 7/25/2024


SC-6 Inlet Protection (IP)



IP-5. OVEREXCAVATION INLET PROTECTION

OVEREXCAVATION INLET PROTECTION INSTALLATION NOTES

1. THIS FORM OF INLET PROTECTION IS PRIMARILY APPLICABLE FOR SITES THAT HAVE NOT YET REACHED FINAL GRADE AND SHOULD BE USED ONLY FOR INLETS WITH A RELATIVELY SMALL CONTRIBUTING DRAINAGE AREA.
2. WHEN USING FOR CONCENTRATED FLOWS, SHAPE BASIN IN 2:1 RATIO WITH LENGTH ORIENTED TOWARDS DIRECTION OF FLOW.
3. SEDIMENT MUST BE PERIODICALLY REMOVED FROM THE OVEREXCAVATED AREA.




IP-6. STRAW BALE FOR SUMP INLET PROTECTION

STRAW BALE BARRIER INLET PROTECTION INSTALLATION NOTES

1. SEE STRAW BALE DESIGN DETAIL FOR INSTALLATION REQUIREMENTS.
2. BALES SHALL BE PLACED IN A SINGLE ROW AROUND THE INLET WITH ENDS OF BALES TIGHTLY ABUTTING ONE ANOTHER.

IP-6 Urban Drainage and Flood Control District
Urban Storm Drainage Criteria Manual Volume 3 August 2013

Inlet Protection (IP) SC-6



CIP-1. CULVERT INLET PROTECTION

CULVERT INLET PROTECTION INSTALLATION NOTES

1. SEE PLAN VIEW FOR:
-LOCATION OF CULVERT INLET PROTECTION.
2. SEE ROCK SOCK DESIGN DETAIL FOR ROCK GRADATION REQUIREMENTS AND JOINTING DETAIL.

CULVERT INLET PROTECTION MAINTENANCE NOTES

1. INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.
2. FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
3. WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.
4. SEDIMENT ACCUMULATED UPSTREAM OF THE CULVERT SHALL BE REMOVED WHEN THE SEDIMENT DEPTH IS $\frac{1}{2}$ THE HEIGHT OF THE ROCK SOCK.
5. CULVERT INLET PROTECTION SHALL REMAIN IN PLACE UNTIL THE UPSTREAM DISTURBED AREA IS PERMANENTLY STABILIZED AND APPROVED BY THE LOCAL JURISDICTION.

(DETAILS ADAPTED FROM AURORA, COLORADO, NOT AVAILABLE IN AUTOCAD)

NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

August 2013 Urban Drainage and Flood Control District
Urban Storm Drainage Criteria Manual Volume 3 IP-7

SC-6 Inlet Protection (IP)

GENERAL INLET PROTECTION INSTALLATION NOTES

1. SEE PLAN VIEW FOR:
-LOCATION OF INLET PROTECTION.
-TYPE OF INLET PROTECTION (IP-1, IP-2, IP-3, IP-4, IP-5, IP-6)
2. INLET PROTECTION SHALL BE INSTALLED PROMPTLY AFTER INLET CONSTRUCTION OR PAVING IS COMPLETE (TYPICALLY WITHIN 48 HOURS). IF A RAINFALL/RUNOFF EVENT IS FORECAST, INSTALL INLET PROTECTION PRIOR TO ONSET OF EVENT.
3. MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

INLET PROTECTION MAINTENANCE NOTES

1. INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.
2. FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
3. WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.
4. SEDIMENT ACCUMULATED UPSTREAM OF INLET PROTECTION SHALL BE REMOVED AS NECESSARY TO MAINTAIN BMP EFFECTIVENESS, TYPICALLY WHEN STORAGE VOLUME REACHES 50% OF CAPACITY, A DEPTH OF 6" WHEN SILT FENCE IS USED, OR $\frac{1}{4}$ OF THE HEIGHT FOR STRAW BALES.
5. INLET PROTECTION IS TO REMAIN IN PLACE UNTIL THE UPSTREAM DISTURBED AREA IS PERMANENTLY STABILIZED, UNLESS THE LOCAL JURISDICTION APPROVES EARLIER REMOVAL OF INLET PROTECTION IN STREETS.
6. WHEN INLET PROTECTION AT AREA INLETS IS REMOVED, THE DISTURBED AREA SHALL BE COVERED WITH TOP SOIL, SEEDED AND MULCHED, OR OTHERWISE STABILIZED IN A MANNER APPROVED BY THE LOCAL JURISDICTION.

(DETAIL ADAPTED FROM TOWN OF PARKER, COLORADO AND CITY OF AURORA, COLORADO, NOT AVAILABLE IN AUTOCAD)

NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

NOTE: THE DETAILS INCLUDED WITH THIS FACT SHEET SHOW COMMONLY USED, CONVENTIONAL METHODS OF INLET PROTECTION IN THE DENVER METROPOLITAN AREA. THERE ARE MANY PROPRIETARY INLET PROTECTION METHODS ON THE MARKET. UDFCD NEITHER ENDORSES NOR DISCOURAGES USE OF PROPRIETARY INLET PROTECTION; HOWEVER, IN THE EVENT PROPRIETARY METHODS ARE USED, THE APPROPRIATE DETAIL FROM THE MANUFACTURER MUST BE INCLUDED IN THE SWAP AND THE BMP MUST BE INSTALLED AND MAINTAINED AS SHOWN IN THE MANUFACTURER'S DETAILS.

NOTE: SOME MUNICIPALITIES DISCOURAGE OR PROHIBIT THE USE OF STRAW BALES FOR INLET PROTECTION. CHECK WITH LOCAL JURISDICTION TO DETERMINE IF STRAW BALE INLET PROTECTION IS ACCEPTABLE.

IP-8 Urban Drainage and Flood Control District
Urban Storm Drainage Criteria Manual Volume 3 August 2013

SHT. NO.
C1.4

DATE: JULY 26, 2024
SCALE: AS NOTED
DESIGN BY: M. UBERATI
DRAWN BY: M. MANNIS
APPROVED BY: M. THORNBROUGH
PROJ. NO.: 24-0008

REVISION
0

RED ROCKS COMMUNITY COLLEGE
GENERATOR ADDITION
EROSION CONTROL DETAILS
BID DOCUMENTS



RMH GROUP
Denver // Phoenix
12600 West Colfax Avenue
Suite A-400
Lakewood, Colorado 80215
Phone 303-239-0909
www.rmhgroup.com © 2024
making a difference through engineeringSM
**Mechanical • Electrical
Industrial • Sustainability**

REV. DATE
07/26/24 ISSUED FOR CONSTRUCTION
DESCRIPTION

MM JOB #: 24-0423.S.01
COPAL: BEN DOWNEY
EOR: BEN DOWNEY
PROJECT MANAGER: JONATHAN OLTMAN

DESIGNERS: JACK MOWAT
CHECKED: 7/23/2024, 10:55:34 PM
DATE PRINTED: Autodesk Docs/MM Structural Projects 2023/04/0423.S.01 - Red Rocks Community College Generator Support - S23.dwg
FILE PATH:

GENERAL NOTES
1) GENERAL: 1A)ENGINEER: REFERENCES ON THE STRUCTURAL DRAWINGS TO "ENGINEER" MEAN THE STRUCTURAL ENGINEER OF RECORD. OTHER ENTITIES ARE SPECIFICALLY NOTED AS "CONTRACTOR'S ENGINEER", "MECHANICAL ENGINEER", ETC. 1B) UNDERGROUND UTILITIES: LOCATE EXISTING UTILITIES AND NOTIFY DESIGN TEAM OF EXISTING UTILITIES OR SUBGRADE CONDITIONS WHICH INTERFERE WITH WORK.
2) USE OF DRAWINGS: 2A)DO NOT SCALE DRAWINGS. 2B)DETAILS ON DRAWINGS TAKE PRECEDENCE OVER GENERAL NOTES AND TYPICAL DETAILS.
3) EXISTING STRUCTURES: 3A)CONTRACT DOCUMENTS HAVE BEEN PREPARED USING AVAILABLE DRAWINGS AND SITE OBSERVATION AS PERMITTED BY ACCESS RESTRICTIONS DURING DESIGN. 3B)DURING CONSTRUCTION, THE CONTRACTOR MAY ENCOUNTER EXISTING CONDITIONS WHICH ARE NOT KNOWN OR ARE AT VARIANCE WITH PROJECT DOCUMENTATION. CONTRACTOR SHALL NOTIFY THE ARCHITECT OF ALL CONDITIONS NOT PER THE CONTRACT DOCUMENTS. EXAMPLES INCLUDE: - SIZES OR DIMENSIONS OTHER THAN THOSE SHOWN - DAMAGE OR DETERIORATION TO MATERIALS AND COMPONENTS - CONDITIONS OF INSTABILITY OR LACK OF SUPPORT ITEMS NOTED AS EXISTING ON THE DRAWINGS BUT NOT FOUND IN THE FIELD 3C)PREPARE DIMENSIONAL DRAWINGS OF ALL DISCOVERED ITEMS. 3D)CONTRACTOR SHALL FIELD VERIFY ALL EXISTING STRUCTURAL CONDITIONS PRIOR TO SUBMITTING SHOP DRAWINGS. 3E)CONTRACTOR SHALL MAKE ALLOWANCE FOR THE RESOLUTION OF SUCH DISCOVERIES IN THE CONSTRUCTION SCHEDULE.
4) COORDINATION: 4A)STRUCTURAL DRAWINGS ARE NOT STAND-ALONE DOCUMENTS AND ARE INTENDED TO BE USED IN CONJUNCTION WITH CIVIL, ARCHITECTURAL, MECHANICAL, ELECTRICAL, AND DRAWINGS FROM OTHER DISCIPLINES. THE CONTRACTOR SHALL COORDINATE ALL REQUIREMENTS OF THE CONTRACT DOCUMENTS INTO SHOP DRAWINGS AND WORK.
5) SUBMITTALS AND SUBSTITUTIONS: 5A)SUBMITTALS: - IF THE CONTRACTOR REQUESTS A CHANGE FROM THE STRUCTURAL DRAWINGS, IT SHALL BE APPROVED BY THE ARCHITECT AND DESIGNED BY MARTIN/MARTIN, INC. PRIOR TO SUBMITTING SHOP DRAWINGS. VARIATION SHALL BE INDICATED ON THE SHOP DRAWINGS. CONTRACTOR SHALL COMPENSATE MARTIN/MARTIN, INC. FOR MAKING THE CHANGE. - CONSTRUCTION DOCUMENTS SHALL NOT BE REPRODUCED FOR USE IN SUBMITTALS - ALL SHOP DRAWINGS SHALL REFERENCE THE STRUCTURAL DRAWING NUMBER AND DETAIL USED TO PREPARE THE SUBMITTAL 5B)SUBSTITUTIONS: APPROVAL SHALL BE SECURED FOR ALL SUBSTITUTIONS 5C)NONCONFORMANCE: NOTIFY ARCHITECT OF CONDITIONS NOT CONSTRUCTED PER THE CONTRACT DOCUMENTS PRIOR TO PROCEEDING WITH CORRECTIVE WORK. SUBMIT PROPOSED REPAIR TO THE ARCHITECT FOR ACCEPTANCE. CONTRACTOR SHALL COMPENSATE MARTIN/MARTIN, INC. FOR DESIGNING THE REPAIR.



QUALITY ASSURANCE GENERAL NOTES
STATEMENT OF STRUCTURAL SPECIAL INSPECTIONS AND TESTING
1. GENERAL: A. SCOPE OF WORK <ul style="list-style-type: none">THE OWNER WILL ENGAGE A QUALIFIED INSPECTION AND TESTING AGENCY(S) TO PERFORM SPECIAL INSPECTIONS AND TESTING FOR ALL STRUTURAL MEMBERS AND ASSEMBLIES AS NOTED HEREIN.SPECIAL INSPECTIONS ARE IN ADDITION TO INSPECTIONS BY THE AUTHORITY HAVING JURISDICTION REQUIRED BY IBC 2021 SECTION 110.
B. SPECIAL INSPECTIONS AND TESTING ARE APPLICABLE TO ALL REVISIONS AND/OR FUTURE WORK ADDED BY AMENDMENTS TO THESE DOCUMENTS.
C. DEFINITIONS <ul style="list-style-type: none">SPECIAL INSPECTOR: THE AGENCY ENGAGED BY THE OWNER AND APPROVED BY THE AUTHORITY HAVING JURISDICTION TO ACT AS THE DESIGNATED REPRESENTATIVE TO PERFORM INSPECTIONS.SPECIAL INSPECTION: INSPECTION PERFORMED BY THE SPECIAL INSPECTOR ACCORDING TO IBC 2021 SECTION 1704 TO ENSURE COMPLIANCE WITH APPROVED CONSTRUCTION DOCUMENTS AND REFERENCED STANDARDS.(P) PERIODIC INSPECTION: THE PART-TIME OR INTERMITTENT OBSERVATION BY THE SPECIAL INSPECTOR OF WORK BEING PERFORMED. SPECIAL INSPECTOR SHALL BE PRESENT IN THE AREA WHERE THE WORK IS BEING PERFORMED. OBSERVATION OF ALL WORK (100% VISUAL) SHALL BE MADE AT THE COMPLETION OF THE WORK.(C) CONTINUOUS INSPECTION: THE FULL-TIME OBSERVATION BY THE SPECIAL INSPECTOR OF WORK BEING PERFORMED. SPECIAL INSPECTOR SHALL BE PRESENT IN THE AREA WHERE THE WORK IS BEING PERFORMED. OBSERVATION OF ALL WORK (100% VISUAL) SHALL BE MADE AT THE COMPLETION OF THE WORK.
D. DEFICIENCIES IN WORK <ul style="list-style-type: none">CORRECT DEFICIENCIES IN WORK THAT TESTS AND INSPECTIONS INDICATE DO NOT COMPLY WITH THE CONTRACT DOCUMENTS AND REFERENCED STANDARDSALL COST OF ADDITIONAL TESTING AND/OR INSPECTIONS FOR CORRECTIVE WORK SHALL BE BORNE BY THE CONTRACTOR.

STRUCTURAL CONCRETE SPECIAL INSPECTIONS - GENERATOR			
ITEM	FREQUENCY	STANDARD	CRITERIA
REINFORCING STEEL			
- DURING PLACEMENT	P	ACI 301-16 3.2-3.3	VERIFY GRADE, FINISH, SIZE, BAR QUANTITY, LOCATION, SPACING, COVER, HOOK LENGTHS, SPLICE LENGTH, SPLICE LOCATIONS, BEND DIAMETERS, COATING, SURFACE CONDITION, AND SUPPORT
- PRIOR TO PLACEMENT OF CONCRETE	100%		
BOLTS AND EMBEDMENTS			
- PRIOR TO PLACEMENT OF CONCRETE	100%	-	VERIFY TYPE, FINISH, DIAMETER, LENGTH, QUANTITY, EMBEDMENT LENGTH, SPACING AND EDGE DISTANCES, VERIFY USE OF PLACING TEMPLATE WHERE SPECIFIED
CONCRETE			
- MIX DESIGN	EACH TRUCK	-	VERIFY USE OF APPROVED DESIGN MIXTURE FOR EACH TRUCK LOAD
- FORMWORK PRIOR TO PLACEMENT OF CONCRETE	P	ACI 301-16 2.2-2.3	INSPECT FIRST POUR OF EACH TYPE (GRADE BEAM, ETC.)
- PLACEMENT OF CONCRETE	C	ACI 301-16 5.3.2	-
- CURING	P	ACI 301-16 5.3.6	-

SOILS SPECIAL INSPECTIONS - GENERATOR			
ITEM	FREQUENCY	STANDARD	CRITERIA
SUBGRADE			
- EXCAVATION	P	-	VERIFY EXCAVATIONS ARE EXTENDED TO THE PROPER DEPTH AND HAVE REACHED THE PROPER BEARING MATERIAL
CONTROLLED FILL			
- PRIOR TO PLACEMENT	P	-	VERIFY SUBGRADE HAS BEEN PROPERLY PREPARED
- PLACEMENT	C	-	VERIFY USE OF PROPER MATERIALS, DENSITIES, COMPACTION, AND LIFT THICKNESSES


CONCRETE NOTES
1) GENERAL: 1A)ALL WORK SHALL CONFORM WITH ACI 301-16, UNLESS NOTED OTHERWISE IN DRAWINGS. 1B)DETAIL BARS IN ACCORDANCE WITH THE DRAWINGS, PROJECT SPECIFICATIONS, AND ACI PUBLICATION SP-86 (2004); "ACI DETAILING MANUAL"
2) REINFORCING MATERIALS: 2A) TYP REINFORCING: ASTM A615, Fy = 60 KSI 2B) EPOXY COATING OF REINFORCING: ASTM A775 OR A934
3) REINFORCING FABRICATION: 3A) SPLICES: - SPLICE PER DETAILS AND WHERE REQUIRED - TYPICAL LAP SPLICE LENGTH = 1'-6" 3B) MISCELLANEOUS REINFORCING REQUIREMENTS: - PROVIDE ADDITIONAL BARS OR STIRRUPS REQUIRED TO SECURE REINFORCING IN PLACE DURING CONCRETE PLACEMENT. - MAKE ALL REINFORCING BAR BENDS IN THE FABRICATOR'S SHOP UNLESS NOTED.
4) STRUCTURAL CONCRETE MIX REQUIREMENTS: 4A) NORMAL WEIGHT CONCRETE - ¾" (#67 AGGREGATE) MAXIMUM. - 28 DAY COMPRESSIVE STRENGTH: 5 KSI. - MAXIMUM WATER/CEMENTITIOUS RATIO: 0.45 - AIR ENTRAINMENT: 6% +/- 1.12%. - MAXIMUM CHLORIDE ION LIMIT: 0.15 - MUST HAVE WORKABILITY AND CONSISTENCY TO PERMIT CONCRETE TO BE WORKED READILY INTO FORMS AND AROUND REINFORCEMENT UNDER CONDITIONS OF PLACEMENT TO BE EMPLOYED, INCLUDING PUMPING, WITHOUT SEGREGATION OR EXCESSIVE BLEEDING. CONTRACTOR SHALL SELECT APPROPRIATE SLUMP. USE ADMIXTURES AS REQUIRED TO OBTAIN DESIRED RESULTS.
5) NON-SHRINK GROUT: 5A) CONFORM TO ASTM C1107 5B) ACHIEVE 6000 PSI COMPRESSIVE STRENGTH AT 28 DAYS.
6) PLACING REINFORCEMENT: 6A) REINFORCEMENT PROTECTION: - SEE DETAILS FOR REBAR COVER - SEE ACI 117-10 FOR REINFORCEMENT PLACING TOLERANCES 6B) PROVIDE ACCESSORIES NECESSARY TO PROPERLY SUPPORT REINFORCING AND WELDED WIRE REINFORCEMENT AT POSITIONS SHOWN ON PLANS. ALL REINFORCING, DOWELS, BOLTS, AND EMBEDDED PLATES SHALL BE SET AND TIED IN PLACE BEFORE THE CONCRETE IS POURED. "STABBING" INTO PREVIOUSLY PLACED CONCRETE IS NOT PERMITTED.
7) MODIFICATIONS TO HARDENED OR EXISTING CONCRETE 7A) UNLESS NOTED ON THE STRUCTURAL DOCUMENTS MODIFICATIONS AS LISTED BELOW SHALL NOT BE MADE TO HARDENED OR EXISTING CONCRETE WITHOUT APPROVAL OF THE DESIGN TEAM: - SAW CUTTING - CORING - CHIPPING 7B) DO NOT CUT OR DAMAGE ANY REINFORCING WITHOUT APPROVAL OF THE DESIGN TEAM
8) SUBMITTALS: 8A) CONCRETE MIX DESIGN INCLUDING: • MIX IDENTIFICATION NUMBER (UNIQUE FOR EACH MIX SUBMITTED). • STATEMENT OF INTENDED MIX USE. • MIXTURE PROPORTIONS. • WATER / CEMENTITIOUS MATERIALS RATIO. • WET AND DRY UNIT WEIGHT. • TOTAL AIR CONTENT. • DESIGN SLUMP AND ALLOWABLE RANGE AFTER ADDITIONS OF ALL ADMIXTURES. • COMPRESSIVE STRENGTH TESTS.

DESIGN CRITERIA
CODES AND STANDARDS: 1A) GENERAL DESIGN - INTERNATIONAL BUILDING CODES 2021 1B) CONCRETE - ACI 301-16 "SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDINGS" - ACI 318-19 "BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE"
2) SEISMIC LOADS - SEISMIC DESIGN CATEGORY = B - RISK CATEGORY = II - EARTHQUAKE IMPORTANCE FACTOR, Ie = 1.0 - MAPPED SPECTRAL RESPONSE ACCELERATION, Ss = 23.4 %g - MAPPED SPECTRAL RESPONSE ACCELERATION, S1 = 6.1 %g - DESIGN SPECTRAL RESPONSE COEFFICIENT, SDs = 0.25 - DESIGN SPECTRAL RESPONSE COEFFICIENT, SD1 = 0.098 - SOIL SITE CLASS = D
3) WIND LOADS - RISK CATEGORY = II - BASIC ULTIMATE WIND SPEED, Vult = 166 mph - BASIC NOMINAL WIND SPEED, Vasd = 138 mph - EXPOSURE CATEGORY = C - INTERNAL PRESSURE COEFFICIENT, Gcpi = +/-0.18 - TOPOGRAPHIC FACTOR, Kzt = 1.00 - ALTITUDE ADJUSTMENT FACTOR, Ke = 0.85
4) SOIL LOADS - ASSUMED ALLOWABLE BEARING PRESSURE OF 1500 PSF PER "PRESUMPTIVE LOAD-BEARING VALUES" TABLE IN IBC 2021 CHAPTER 18

	
<div>1</div> <div>1/4" = 1'-0"</div> <div>GENERATOR PLAN - NEW</div>	
	
2	3/4" = 1'-0" GENERATOR PAD EXTENSION

		REV	DATE	DESCRIPTION
			07/26/24	ISSUED FOR CONSTRUCTION
<div>Denver // Phoenix 12600 West Colfax Avenue Suite A-400 Lakewood, Colorado 80215 Phone 303-239-0909 www.rmhgroup.com © 2024 making a difference through engineeringSM</div> <div>RMH GROUP</div> <div>Mechanical • Electrical Industrial • Sustainability</div>				
<div>MARTIN/MARTIN CONSULTING ENGINEERS</div> <div>Lakewood, Colorado 80215 martinmartin.com</div>				
<div>RED ROCKS COMMUNITY COLLEGE GENERATOR ADDITION</div> <div>13300 W 6TH AVE. LAKEWOOD, CO 80228</div> <div>STRUCTURAL PLANS DETAILS AND NOTES</div>				
Date: JULY 26, 2024	Scale: As indicated	Designed By: JO	Drawn By: JM	Approved By: BDU/JO
SHT NO: S1.0		Project No: 24-0423.S.01		
		REVISION		

<




1 MECHANICAL SITE PLAN
SCALE: 3/16" = 1'-0"

SHEET NOTES

1. LIGHT LINE WEIGHT INDICATES EXISTING. HEAVY LINE WEIGHT INDICATES NEW CONSTRUCTION.
2. REPAIR ALL SURFACES AND FINISHES DAMAGED DUE TO DEMOLITION OR CONSTRUCTION TO MATCH EXISTING CONDITIONS.
3. EQUIPMENT AND PIPING SHOWN ON THIS DRAWING ARE BASED ON RECORD INFORMATION PROVIDED IN PART BY OTHERS. THE CONTRACTOR IS RESPONSIBLE FOR FIELD VERIFICATION OF EXISTING CONDITIONS PRIOR TO STARTING WORK AND SHALL NOTIFY THE ARCHITECT/ENGINEER OF ANY DISCREPANCIES FOR RESOLUTION.

KEY NOTES

- 1 NEW PENETRATION OF EXISTING CONCRETE PAD / BOILER ROOM ROOF / DECK FOR NEW 2" GAS LINE. CORE DRILL CONCRETE. X-RAY PRIOR TO DRILLING TO PROPERLY LOCATE CLEAR AREA FOR PENETRATION. AFTER PIPE INSTALLATION, SEAL OPENING SUCH THAT THE SEAL IS WATER TIGHT.
- 2 PROVIDE TEE WITH SEDIMENT TRAP PER 2021 IFGC 408.4.
- 3 GAS SHUT OFF VALVE AND REGULATORS SHALL BE APPROXIMATELY 3'-0" ABOVE CONCRETE PAD AND SHALL BE SUPPORTED APPROPRIATELY WITH UNISTRUT SUPPORTS SECURED TO CONCRETE OR PREFABRICATED PIPE SUPPORTS (DURABLOCK OR SIMILAR).
- 4 GAS TO ROUTE DOWN AND LOW PRIOR TO GENERATOR CONNECTION TO AVOID CONFLICT WITH GENERATOR ACCESS DOORS.
- 5 CUT IN NEW GAS PIPING TEE AND ROLL DOWN WITH AT A 45 DEGREE ANGLE TO NEW GAS SHUT OFF VALVE AS SHOWN.
- 6 CONTROLS NOTE: PROVIDE NEW STATUS FROM GENERATOR TO THE EXISTING BUILDING BAS. CONTROLS CONTRACTOR SHALL BE UNIVERSAL CONTROLS.



KEY PLAN

RED ROCKS COMMUNITY COLLEGE GENERATOR ADDITION

13300 W. 6TH AVE., LAKEWOOD, CO 80228

MECHANICAL SITE PLAN

RMH GROUP
Denver // Phoenix
12600 West Colfax Avenue
Suite A-400
Lakewood, Colorado 80215
Phone 303-239-0909
www.rmhgroup.com © 2024
making a difference through engineeringSM

Mechanical • Electrical
Industrial • Sustainability

DATE: JULY 26, 2024	SCALE: NONE	DESIGN BY: NLS	DRAWN BY: NLS	APPROVED BY: MJU	PROJ. NO.: 21058
---------------------	-------------	----------------	---------------	------------------	------------------

SHT. NO.	REVISION
M01	1

REV.	DATE	ISSUED FOR	CONSTRUCTION	DESCRIPTION
	07/26/24			

DATE: JULY 26, 2024	
SCALE: NONE	
DESIGN BY: NLS	
DRAWN BY: NLS	
APPROVED BY: MWJ	
PLT. NO: 21098	
SHT.NO.	REVISION
M60	—

**RED ROCKS COMMUNITY COLLEGE
GENERATOR ADDITION**
13300 W. 6TH AVE., LAKEWOOD, CO 80228
MECHANICAL SCHEDULES



GAS REGULATOR SCHEDULE								
TAG	SERVICE	LINE SIZE (IN)	PRESSURE		MAX FLOW (SCFH)	MIN FLOW (SCFH)	MANUFACTURER & MODEL	NOTES
			INLET (PSIG)	OUTLET (PSIG)				
GR-1	GENERATOR	2"	10	1.5	5615	3002	EMERSON FISCHER CS-800	1
<u>NOTES:</u> 1. OUTLET PRESSURE IS MAX ALLOWABLE AT GENERATOR.								


Created on 6/19/2024, 10:58:10 AM
File: E00.dwg
User: T:\Users\Terry\Documents
Plotted on 6/17/2025

ELECTRICAL LEGEND (NOTE: NOT ALL SYMBOLS SHOWN ARE USED ON THESE DRAWINGS)										
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	
- ONE LINE SYMBOLS -		- GENERAL -		- SPECIAL SYSTEMS DEVICES -		- POWER -		- LIGHTING - (REFER TO LUMINAIRE SCHEDULE)		
	CIRCUIT BREAKER		BRANCH CIRCUIT HOME RUN TO PANELBOARD, DESIGNATION INDICATES PANEL AND CIRCUIT NUMBERS		DATA OUTLET		DUPLEX RECEPTACLE D = DEDICATED CIRCUIT IG = ISOLATED GROUND DEVICE AC = AUTOMATICALLY CONTROLLED RECEPTACLE		LUMINAIRE X = FIXTURE DESIGNATION B = BRANCH CIRCUIT NUMBER S = SWITCH LEG IDENTIFIER	
	DRAW-OUT CIRCUIT BREAKER (MOLDED INSULATED CASE)		CONTROL WIRING		COMBINATION TELEPHONE/DATA OUTLET		GFI = GROUND FAULT CIRCUIT INTERRUPTER		SHADING INDICATES LUMINAIRE ON LIFE SAFETY	
	DRAW-OUT POWER CIRCUIT BREAKER		LIGHTING, ONE-LINE, AND POWER CIRCUITING		TELEVISION JACK		FLOOR MOUNTED DUPLEX RECEPTACLE		SHADING INDICATES PORTION OF LUMINAIRE ON LIFE SAFETY	
	CONTROL FUSE		LIGHTING, ONE-LINE, AND POWER CIRCUITING (UNDERGROUND)		CEILING MOUNTED DATA OUTLET		FLOOR MOUNTED SPECIAL PURPOSE RECEPTACLE		WALL MOUNTED LUMINAIRE	
	FUSE WITH SWITCH		FLEXIBLE CONDUIT		CEILING MOUNTED TELEPHONE/DATA OUTLET		CEILING MOUNTED DUPLEX RECEPTACLE		STRIP LIGHT	
	SWITCH		CONDUIT BREAK SYMBOL		CEILING MOUNTED TELEPHONE OUTLET		CEILING MOUNTED FOURPLEX RECEPTACLE		STRIP LIGHT WITH LIFE SAFETY	
	PANELBOARD		CONDUIT CAP		FLOOR MOUNTED DATA OUTLET		CEILING MOUNTED SPECIAL PURPOSE RECEPTACLE		POLE MOUNTED LUMINAIRE (QUANTITY OF LUMINAIRES PER POLE AS INDICATED ON PLANS)	
	AUTOMATIC TRANSFER SWITCH		CONDUIT CHANGE IN ELEVATION		FLOOR MOUNTED TELEPHONE/DATA OUTLET		FOURPLEX RECEPTACLE		DOWNLIGHT LUMINAIRE	
	FEEDER DESIGNATION, SEE FEEDER SCHEDULE		CONDUIT STUB DOWN (OUT OF DRAWING LIMITS)		FLOOR MOUNTED TELEPHONE OUTLET		RANGE RECEPTACLE		WALL WASHER LUMINAIRE	
	AUTOMATIC TRANSFER SWITCH WITH BY-PASS		CONDUIT STUB UP (OUT OF DRAWING LIMITS)		TELEPHONE TERMINAL BOARD		SINGLE RECEPTACLE		ADJUSTABLE LUMINAIRE	
	ENGINE GENERATOR		JUNCTION BOX		DATA TERMINAL BOARD		SWITCHED RECEPTACLE		PENDANT LUMINAIRE	
	TRANSFORMER		WALL MOUNTED JUNCTION BOX		MICROPHONE OUTLET		DUPLEX EMERGENCY/CRITICAL		TRACK LIGHTING	
	ENCLOSED BUSWAY		PUSH BUTTON A = ABORT DA = DURESS ALARM EPO = EMERGENCY POWER OFF IC = INTERCOM ST = SHUNT TRIP		SPEAKER V = WITH INTEGRAL VOLUME CONTROL		FOURPLEX EMERGENCY/CRITICAL		PHOTOCELL	
	GROUND BUS		SWITCH SYMBOL (#) S = SINGLE POLE (IF BLANK) D = DOUBLE POLE 3 = THREE-WAY 4 = FOUR-WAY AS = ADJUSTABLE SPEED D = DIMMER K = KEY OPERATED LV = LOW VOLTAGE M = MANUAL MOTOR SWITCH OS = OCCUPANCY SENSOR P = WITH PILOT LIGHT T = TIMER TO = THERMAL OVERLOAD WP = WEATHERPROOF x = SMALL LETTER - LUMINAIRES CONTROLLED XP = EXPLOSION PROOF		WALL MOUNTED SPEAKER		DUPLEX 2-PORT USB		EXIT LIGHT (WITH FACES AND DIRECTION ARROWS INDICATED)	
	WEATHERHEAD		DIAL SWITCH		CLOCK RECEPTACLE OUTLET		4-PORT USB		WALL MOUNTED EXIT LIGHT (WITH FACES AND DIRECTION ARROWS INDICATED)	
	MOTOR		INTERCOM SWITCH		SECURITY CAMERA		DISCONNECT SWITCH		WALL MOUNTED BATTERY PACK EMERGENCY LIGHT	
	DELTA CONNECTION	- FIRE ALARM DEVICES -			THERMOSTAT		FUSED DISCONNECT SWITCH	- GROUNDING SYMBOLS -		
	WYE CONNECTION		BELL			MOTOR STARTER		COMBINATION MOTOR STARTER		GROUNDING CONDUCTOR
	GROUND WYE CONNECTION		DUCT SMOKE DETECTOR		COMBINATION FIRE HORN/STROBE LIGHT		CONDUIT SEAL OFF		LIGHTNING PROTECTION AIR TERMINAL	
	GROUND WYE CONNECTION WITH RESISTOR GROUND		FIRE FIGHTER'S TELEPHONE JACK		COMBINATION FIRE SPEAKER/STROBE LIGHT		FIRE RATED POKE-THROUGH		BONDING POINT	
	GROUND WYE CONNECTION WITH REACTOR GROUND		FIRE ALARM STROBE LIGHT		FIRE ALARM STROBE/SPEAKER, CEILING MOUNT		PARTITION CIRCUIT SPLIT		GROUND BAR	
	METERING DEVICE		FIRE ALARM STROBE, CEILING MOUNT		FIRE ALARM STROBE/SPEAKER, CEILING MOUNT		POWER POLE		ELECTRICAL GROUND	
	CURRENT TRANSFORMER		FIRE HORN		DUAL PROJECTION FIRE HORN		SURFACE RACEWAY		GROUND ROD	
	POTENTIAL TRANSFORMER		MANUAL PULL STATION		MAGNETIC DOOR HOLD OPEN		- NURSE CALL -		GROUND ROD WITH INSPECTION TEST WELL	
	LOAD-BREAK CONNECTOR		DETECTOR UNDER FLOOR F = FLAME I = IONIZATION TYPE P = PHOTOELECTRIC TYPE T = THERMAL TYPE		DETECTOR UNDER FLOOR		CODE BLUE STATION		PIGTAIL	
	PROTECTIVE RELAY DEVICE		DETECTOR UNDER FLOOR		DETECTOR UNDER FLOOR		CODE PINK STATION	- EQUIPMENT -		
	KEY INTERLOCK		DETECTOR UNDER FLOOR		DETECTOR UNDER FLOOR		EMERGENCY CALL PULL STATION		DISTRIBUTION PANEL	
	RESISTOR		DETECTOR UNDER FLOOR		DETECTOR UNDER FLOOR		SINGLE PATIENT STATION		EXISTING DISTRIBUTION PANEL	
	CONTACT NORMALLY OPEN		DETECTOR UNDER FLOOR		DETECTOR UNDER FLOOR		STAFF ASSIST STATION		NEW PANEL, FLUSH MOUNTED	
	CONTACT NORMALLY CLOSED		DETECTOR UNDER FLOOR		DETECTOR UNDER FLOOR		AUXILIARY INPUT STATION		EXISTING PANEL, FLUSH MOUNTED	
	CAPACITOR		DETECTOR UNDER FLOOR		DETECTOR UNDER FLOOR		DUTY STATION		NEW PANEL, SURFACE MOUNTED	
	SINGLE BATTERY		DETECTOR UNDER FLOOR		DETECTOR UNDER FLOOR		STAFF STATION		EXISTING PANEL, SURFACE	
	MULTIPLE BATTERIES		DETECTOR UNDER FLOOR		DETECTOR UNDER FLOOR		BED INTERFACE STATION		TRANSFORMER	
	LIGHTNING ARRESTOR		DETECTOR UNDER FLOOR		DETECTOR UNDER FLOOR		TWO BUTTON STATION			
	THERMAL ELEMENT, OVERLOAD RELAY		DETECTOR UNDER FLOOR		DETECTOR UNDER FLOOR		BED MANAGEMENT STATION			
			DETECTOR UNDER FLOOR		DETECTOR UNDER FLOOR		DOMELIGHT			
			DETECTOR UNDER FLOOR		DETECTOR UNDER FLOOR		ZONE LIGHT INTERSECTION			
			DETECTOR UNDER FLOOR		DETECTOR UNDER FLOOR		REMOTE LOCATOR			
			DETECTOR UNDER FLOOR		DETECTOR UNDER FLOOR		PATIENT MONITOR			

APPLICABLE CODES		
AHJ: STATE OF COLORADO		
FIRE AUTHORITY: WEST METRO FIRE DISTRICT		
REMODEL	<input checked="" type="checkbox"/>	NEW
YEAR	CODE	
2021	INTERNATIONAL BUILDING CODE	
2021	INTERNATIONAL MECHANICAL CODE	
2021	INTERNATIONAL PLUMBING CODE	
2021	INTERNATIONAL ELECTRICAL CODE	
2021	INTERNATIONAL FIRE CODE	
2023	NATIONAL ELECTRICAL CODE	
2021	INTERNATIONAL ENERGY CONSERVATION CODE	
IS THE BUILDING FULLY SPRINKLERED? <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO		
IS THE BUILDING FULLY DETECTED? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO		
- GRAPHIC SYMBOLS -		
	KEY NOTE	
	REVISION NUMBER	
	DETAIL NOTE	
	X = DENOTES ALL LUMINAIRES IN THE RESPECTIVE AREA ARE THE TYPE INDICATED, REFER TO LUMINAIRE SCHEDULE	
	PANEL FLAG	
	OWNER EQUIPMENT TAG	
	LIGHTING CONTROL SEQUENCE INDICATION, SET LIGHTING CONTROL SEQUENCE OF OPERATION SCHEDULE FOR INFORMATION	
	MECHANICAL EQUIPMENT TAG	
	SHADING INDICATES EQUIPMENT	
	HATCHING INDICATES ITEM(S) TO BE REMOVED	
	ROOM NUMBER	
	NORTH ARROW	
	DETAIL BUBBLE	
	SECTION NUMBER - WHERE DETAIL IS SHOWN	
	SECTION CUT	
	SECTION NUMBER/LETTER	
GENERAL NOTES		
SPECIFICATIONS ARE A PART OF THE CONSTRUCTION DOCUMENTS. SHOULD ANY CONFLICT ARISE BETWEEN THE DRAWINGS AND SPECIFICATIONS, BRING SUCH CONFLICT TO THE ATTENTION OF THE ENGINEER FOR RESOLUTION, UNLESS OTHERWISE DIRECTED BY ENGINEER, THE MOST STRINGENT REQUIREMENT WILL PREVAIL.		
DATA ON THE DRAWINGS IS AS EXACT AS COULD BE REASONABLY SECURED. ABSOLUTE ACCURACY IS NOT GUARANTEED. VERIFY EXACT LOCATIONS, MEASUREMENTS, LEVELS, SPACE REQUIREMENTS, POTENTIAL CONFLICTS WITH OTHER TRADES, ADAPT WORK TO ACTUAL CONDITIONS AT THE SITE, BEFORE SUBMITTING COSTS VISIT THE SITE TO BECOME THOROUGHLY FAMILIAR WITH THE ACTUAL CONDITIONS OF THIS PROJECT. THESE DRAWINGS ARE DIAGNOSTIC IN NATURE, DO NOT SCALE. THESE DRAWINGS DO NOT SHOW MATERIALS FOR A COMPLETE INSTALLATION. PLAN THE INSTALLATION AND LAYOUT OF THE WORK AS DIAGRAMMED IN THESE DOCUMENTS. REFER TO FLOOR PLANS, SCHEMATICS AND DIAGRAMS OF OTHER TRADES FOR ELECTRICAL REQUIREMENTS, BRANCH CIRCUITS AND OTHER ELECTRICAL CONNECTIONS NOT INDICATED ON THESE DOCUMENTS.		
FIRE-SEAL ALL PENETRATIONS THROUGH RATED WALLS AND FLOORS WITH MATERIALS CAPABLE OF PREVENTING THE PASSAGE OF FLAMES AND HOT GASES WHEN SUBJECTED TO THE REQUIREMENTS OF THE TEST STANDARD SPECIFIC FOR FIRE STOPS ASTM E814.		
EXECUTE THE WORK IN ACCORDANCE WITH SUPPORTING OBJECTS FOR SEISMIC ZONE REQUIRED BY STATE AND LOCAL CODES ALL CEILING ATTACHED OBJECTS AND FLOOR ATTACHED EQUIPMENT INCLUDING, BUT NOT LIMITED TO: PENDANT LIGHTING FIXTURES, GENERAL LIGHTING, MULTIPLE RACKWAYS, GENERATOR, TRANSFORMER, ELECTRICAL SWITCHGEAR, SWITCHBOARDS AND OTHER ELECTRICAL EQUIPMENT.		
WHERE DISCONNECTS ARE INDICATED ON DRAWINGS PROVIDE FINAL CONNECTION TO EQUIPMENT BEING DISCONNECTED. FINAL DISCONNECTING MEANS FOR ALL MECHANICAL EQUIPMENT SHALL BE ACCESSIBLE AND HAVE THE CLEARANCE REQUIRED BY NEC.		
UP-TO-DATE ELECTRICAL RECORD DRAWINGS ARE NOT AVAILABLE FOR THIS PROJECT. INFORMATION FOR EXISTING CIRCUITRY IS BASED ON EXISTING PANEL DIRECTORIES, AVAILABLE DRAWINGS, AND ASSUMPTIONS.		
LOCATIONS AND INFORMATION FOR EXISTING ELECTRICAL DEVICES AND EQUIPMENT SHOWN ON THESE DOCUMENTS ARE APPROXIMATE AND WERE DERIVED FROM FIELD OBSERVATION AND AVAILABLE RECORD DRAWINGS. VERIFY ACTUAL FIELD CONDITIONS PRIOR TO STARTING WORK.		

REV: 06/24/2020

COPYRIGHT, THE RHM GROUP, INC. 2022




SHEET NOTES

1. LIGHT LINE WEIGHT INDICATES EXISTING. HEAVY LINE WEIGHT INDICATES NEW CONSTRUCTION.
2. INCLUDE ALL COST, LABOR, MATERIAL, SERVICE ENTRANCE INSTALLATION, CONNECTION, FINAL TERMINATION, START-UP, TESTING, PERMIT FEES, AND ALL OTHER APPLICABLE FEES.
3. LOCATE ALL EXISTING UNDERGROUND UTILITIES PRIOR TO TRENCHING AND INSTALL ALL UNDERGROUND RACEWAYS IN MOST FEASIBLE LOCATION.
4. COORDINATE ELECTRICAL EQUIPMENT LOCATIONS AND UNDERGROUND ROUTING WITH UTILITIES AND OTHER TRADES PRIOR TO TRENCHING AND SETTING EQUIPMENT PADS.
5. PATCH AND PAINT ANY DAMAGED SURFACES DUE TO DEMOLITION AND CONSTRUCTION TO MATCH EXISTING CONDITIONS.
6. PROVIDE ALL TRENCHING, BACKFILL AND SAW CUTTING. RETURN ALL LANDSCAPING, PAVEMENT, AND FLATWORK BACK TO ITS ORIGINAL CONDITION AT NO ADDITIONAL COST TO THE OWNER.
7. UNLESS OTHERWISE INDICATED, ALL CONDUCTORS FOR BRANCH CIRCUITS SHALL BE #12 AWG, PROTECTED BY 20-AMPERE CIRCUIT BREAKERS. INCREASE CONDUCTOR SIZE TO ACCOUNT FOR VOLTAGE DROP FOR ALL 120-VOLT CIRCUITS OVER 75 FEET, AND ALL 277-VOLT CIRCUITS OVER 150 FEET TO THE FIRST OUTLET. CONDUCTOR SIZE SHALL BE UNIFORM FOR THE ENTIRE LENGTH OF THE CIRCUIT UNLESS NOTED OTHERWISE. HOMERUNS WHICH INDICATE UPGRADING CIRCUIT CONDUCTORS FOR VOLTAGE DROP, E.G., #10AWG WIRE ON 20-AMPERE CIRCUIT, SHALL HAVE THE CONDUCTOR SIZE INDICATED CARRIED THROUGHOUT THE CIRCUIT TO ALL JUNCTION BOXES UP TO AND INCLUDING THE J-BOX NEAREST THE LAST DEVICE OR LUMINAIRE.

KEY NOTES

- 1 REFEEED EXISTING EQUIPMENT FROM NEW GENERATOR BACKED PANELBOARDS.
- 2 PROVIDE A 1" CONDUIT AND DEDICATED CIRCUITS FOR CONNECTION TO GENERATOR BATTERY CHARGER, BLOCK HEATER, AND LIGHTING/RECEPTACLE. COORDINATE FINAL REQUIREMENTS WITH SELECTED GENERATOR.
- 3 PROVIDE 1" CONDUIT BETWEEN THE GENERATOR AND ANNUNCIATOR PANEL. COORDINATE CONDUCTOR/CABLE REQUIREMENTS WITH THE SELECTED GENERATOR.
- 4 PROVIDE 2 2-1/2" CONDUITS BETWEEN THE GENERATOR AND ATS. SEE ONE-LINE DIAGRAM FOR ADDITIONAL INFORMATION ON POWER FEEDER. COORDINATE CONTROLS CONDUCTOR/CABLE REQUIREMENTS WITH THE SELECTED GENERATOR.
- 5 PROVIDE PENETRATIONS AND SEALS THROUGH EXISTING FOUNDATION WALL.
- 6 INTEGRATE GENERATOR ANNUNCIATOR AND EXISTING BAS. COORDINATE INTEGRATION WITH OWNER, CAMPUS IT DEPARTMENT, AND OWNER'S CONTROLS CONTRACTOR, UNIVERSAL CONTROLS.
- 7 PROVIDE GENERATOR EMERGENCY POWER OFF (EPO) BUTTON WITH WEATHER-PROOF ENCLOSURE.
- 8 REPLACE EXISTING RECEPTACLE WITH A GFCI RECEPTACLE. MAINTAIN THE EXISTING CIRCUIT.



KEY PLAN

1 ELECTRICAL SITE PLAN
E01 SCALE: 3/16" = 1'-0"

RED ROCKS COMMUNITY COLLEGE
GENERATOR ADDITION
13300 W. 6TH AVE., LAKEWOOD, CO 80228


RMH GROUP
Denver // Phoenix
12600 West Colfax Avenue
Suite A-400
Lakewood, Colorado 80215
Phone 303-239-0909
www.rmhgroup.com © 2024
making a difference through engineeringSM
Mechanical • Electrical
Industrial • Sustainability

REV.	DATE	DESCRIPTION
ADD 01	ISSUED FOR BID 07/29/24	ISSUED FOR CONSTRUCTION


SHT.NO.	REVISION
E01	1

DATE: JULY 26, 2024	SCALE: 3/16" = 1'-0"
DESIGN BY: CPB	DRAWN BY: EE
APPROVED BY: SB	PROJ. NO.: 21098


Created on 10/16/2025
File Path: C:\Users\jgarcia\OneDrive\Documents\RedRocks\Generator\Generator.dwg
Sheet: 15 of 15
Plotted on 10/17/2025




1 4-Pole Transfer Switch Grounding Diagram
ES1 SCALE: NONE



3 Conduit Support Detail
ES1 SCALE: NONE



2 Device Labeling Detail
ES1 SCALE: NONE
NOTE: LABEL WITH BROTHER "P-TOUCH" SYSTEM. PROVIDE CLEAR OR WHITE TAPE WITH BLACK LETTERING.



4 Panel/Equipment Nameplate Detail
ES1 SCALE: NTS
NOTE: REWORD NAMEPLATE TO MATCH ACTUAL EQUIPMENT.

DATE: JULY 26, 2024
SCALE: NONE
DESIGN BY: CPB
DRAWN BY: EKE
APPROVED BY: SB
PRJ. NO: 21088

SHT. NO.
E51
REVISION
1

RED ROCKS COMMUNITY COLLEGE
GENERATOR ADDITION
13300 W. 6TH AVE., LAKEWOOD, CO 80228
ELECTRICAL DETAILS

RMH GROUP
Mechanical • Electrical
Industrial • Sustainability
Denver // Phoenix
12600 West Colfax Avenue
Suite A-400
Lakewood, Colorado 80215
Phone 303-239-0909
www.rmhgroup.com © 2024
making a difference through engineeringSM

10/20/2025
ADD 01 - ISSUED FOR BID
07/29/24
ISSUED FOR CONSTRUCTION
REV. DATE DESCRIPTION

Version_082

NOTES:

1. COORDINATE ELECTRICAL EQUIPMENT REQUIREMENTS WITH THE ACTUAL MECHANICAL EQUIPMENT SUPPLIED

SHORT CIRCUIT CALCULATIONS BASED ON BUESSMANN POINT TO POINT METHOD

Version V.0226

SHORT CIRCUIT SCHEDULE

Fault Contribution

Utility contribution: 1500 kVA, 480 V, 3 PH, 3.5%Z

33,900 A

Total fault current from all sources

33,900 A

Point Fault Calculations

POINT/DESCRIPTION	Required Short Circuit Rating	Short Circuit I _{SC} RMS	S _{SC} MVA	F Factor	Constant C	Voltage V (V)	Length of Run (ft)	Available I _{SC} (A)	X/R Ratio	X/R Impedance %
X1 Service XFMTR to MDC	42,000	32,889	0.973	0.026	177,480	480	40	33,900
X2 MDC to ATS	42,000	31,954	0.969	0.03	25,686	480	7	32,990
X3 ATS to HPG	35,000	31,252	0.978	0.022	25,686	480	5	31,954
X4 HPG to PRIMARY 30kVA XFMR	30,000	25,816	0.808	0.238	2,425	480	5	31,954
X5 30kVA XFMR	5,000	2,288	0.089	25,040	25,816	30	3.5
X6 SECONDARY 30kVA XFMR to LPG	5,000	2,258	0.987	0.013	7,292	208	5	2,288
X7 LPGA to CU-1	22,000	16,301	0.586	0.708	8,924	480	56	31,252
X8 HPG to CHMP-6	5,000	3,332	0.106	8,408	31,252
X9 HPG to CHMP-7	5,000	2,924	0.094	9,667	31,252
X10 HPG to PRIMARY PDU XFMR	30,000	23,889	0.755	0.325	12,843	480	37	31,252
X11 PDU XFMR	14,000	9,763	0.414	4,576	23,889	150	3.5
X12 SECONDARY PDU XFMR to POU	10,000	8,640	0.885	0.130	39,406	208	63	9,763
X13 HPG to PRIMARY UPS XFMR	25,000	21,986	0.703	0.421	12,843	480	48	31,252
X14 UPS XFMR	14,000	9,637	0.438	4,265	21,986	150	3.5
X15 SECONDARY UPS XFMR to UPS	10,000	8,480	0.890	0.135	39,406	208	67	9,637
X16 MDC to MCC	35,000	26,688	0.900	0.111	12,843	480	12	32,990
X17 LPGA to CU-1	5,000	470	0.208	3,810	2,258
X18 LPGA to CU-2	5,000	680	0.301	2,320	2,258


EQUIPMENT SCHEDULE																Version 06/23				
KEY	EQUIPMENT DESCRIPTION (SEE NOTE 1)	VOLTS	FPH	LOAD TYPE	UNIT FLA	UNIT KVA	UNIT KW	PANEL (SEE NOTE 2)	BREAKER SIZE	EQUIPMENT FEEDER	MINIMUM SCOR (RA) (SEE NOTE 1)				STARTER / CONTROLLER		MOTOR FEEDER	LOCAL DISC. SW (SEE NOTE 3)	DISC LOCATION (SEE NOTE 4)	REMARKS
											TYPE	SIZE	LOCATION	TYPE	SIZE	LOCATION				
CU-1	CONDENSING UNIT	200	1	M	12.0	2.4	1.9	LPG	20	3/4 C - 2#12, 1#12G	5	-	-	-	AT UNIT	3/4 C - 2#12, 1#12G	20A, 2P	AT UNIT	--	
CU-2	CONDENSING UNIT	200	1	M	20.0	4.0	3.2	LPG	30	3/4 C - 2#10, 1#10G	5	-	-	-	AT UNIT	3/4 C - 2#10, 1#10G	30A, 2P	AT UNIT	--	

NOTES:

- COORDINATE ELECTRICAL EQUIPMENT REQUIREMENTS WITH THE ACTUAL MECHANICAL EQUIPMENT SUPPLIED. VERIFY THE COMPONENT OR EQUIPMENT MARKED NAMEPLATE SCOR IS EQUAL TO OR GREATER THAN THE AVAILABLE FAULT CURRENT INDICATED. IF THE NAMEPLATE SCOR IS LESS THAN THE AVAILABLE FAULT CURRENT, PROTECT COMPONENT OR EQUIPMENT TO AVAILABLE SHORT-CIRCUIT CURRENT INDICATED ACCORDING TO ANSI/UL 508A, SUPPLEMENT SB, USING NRTL LISTED COMPONENTS. SUBMIT FOR REVIEW COMPONENTS DATA AND TIME-CURRENT CURVES SUBSTANTIATING COMPLIANCE.
- REFER TO PANEL SCHEDULES FOR EXACT CIRCUIT NUMBER.
- IF A FUSE SIZE IS INDICATED, PROVIDE A FUSED DISCONNECT UNLESS INDICATED OTHERWISE.
- FUSE SIZE INDICATED MUST BE USED IN COMBINATION WITH PROPERLY SIZED OVERLOAD RELAYS. UNLESS INDICATED OTHERWISE, FUSES SHALL BE BUSSMANN LPS-RK OR LPN-RK. CONFIRM ACTUAL NAMEPLATE DATA OF EQUIPMENT AND PROVIDE FUSES RECOMMENDED BY MANUFACTURER.

PANEL LOAD SUMMARY					NEC DEMAND LOAD SUMMARY					
LOAD TYPE	PH A	PH B	PH C	TOTAL	LOAD TYPE	KW	POWER FACTOR	DEMAND FACTOR	CALCULATED	
LIGHTING	0.0	0.0	0.2	0.2	KVA	0.0	95%	0.7	125% = 0.3	
REFRIGERATE	0.0	0.0	0.0	0.0	LIGHTING	0.0	95%	0.7	125% = 0.3	
COMPUTER	0.0	0.0	0.0	0.0	RECEPTABLES	1.9	95% = 2.0	100% = 2.0	KVA	
MOTOR	31.0	31.2	32.4	94.5	FIRST 10 KW	1.9	95% = 2.0	100% = 2.0	KVA	
KITCHEN	0.0	0.0	0.0	0.0	REMAINDER	0.0	95% = 0.0	50% = 0.0	KVA	
NONCONCIDENT	0.0	0.0	0.0	0.0	COMPUTER	0.0	95% = 0.0	125% = 0.0	KVA	
EQUIPMENT	0.0	0.0	0.0	0.0	MOTORS	63.8	80% = 79.8	125% = 100	KVA	
OTHER	33.8	33.8	33.3	101	LARGEST	63.8	80% = 79.8	125% = 100	KVA	
COND. LOAD	0.0	0.0	0.0	0.0	REMAINDER	11.8	80% = 14.7	100% = 14.7	KVA	
NONCONCIDENT	0.0	0.0	0.0	0.0	KITCHEN	0.0	95% = 0.0	50% = 0.0	KVA	
PEAK LOAD	0.0	0.0	0.0	0.0	HEAT	10.0	100% = 1.0	125% = 13	KVA	
TOTAL	66.3	66.3	66.9	199	EQUIPMENT	0.0	85% = 0.0	100% = 0.0	KVA	
					OTHER	85.5	85% = 101	100% = 101	KVA	
PHASE BALANCE					0.0	85% = 0.0	100% = 0.0	125% = 0.0	KVA	
					NONCONCIDENT	0.0	95% = 0.0	0% = 0.0	KVA	
					PEAK LOAD	0.0	95% = 0.0	125% = 0.0	KVA	
					0.0	0% Spare	0.0	90% = 0.0	100% = 0.0	KVA
					TOTAL	165	90% = 159	KVA	215	KVA
MIN PANEL AMPS REQUIRED										

PANEL LOADING SUMMARY					NEC DEMAND LOAD SUMMARY				
LOAD TYPE	PH A	PH B	PH C	TOTAL	LOAD TYPE	POWER KW	FACTOR	DEMAND KVA	CALCULATED
LIGHTING	0.0	0.0	0.2	0.2 KVA	LIGHTING	0.2	95%	0.2	0.3 KVA
RECEP	14.0	0.5	0.2	2.2 KVA	RECEPABLES				
COMPUTER	0.0	0.0	0.0	0.0 KVA	FIRST 10 KVA	21.0	95%	2.2	10.0 KVA
MOTOR	19.0	2.0	3.2	7.1 KVA	REMAINDER	0.0	95%	0.0	50% = 0.0 KVA
KITCHEN	0.0	0.0	0.0	0.0 KVA	COMPUTER	0.0	95%	0.0	125% = 0.0 KVA
HEAT	0.0	0.0	0.0	0.0 KVA	MOTORS				
EQUIPMENT	0.0	0.0	0.0	0.0 KVA	LARGEST	32.0	80%	4.0	125% = 5.0 KVA
OTHER	0.5	0.5	0.0	1.0 KVA	REMAINDER	25.0	80%	3.1	100% = 3.1 KVA
COND LOAD	0.0	0.0	0.0	0.0 KVA	KITCHEN	0.0	95%	0.0	125% = 0.0 KVA
PEAK LOAD	0.0	0.0	0.0	0.0 KVA	HEAT	10.0	100%	1.0	125% = 1.3 KVA
TOTAL	38.4	4.0	3.6	11.4 KVA	EQUIPMENT	0.0	85%	0.0	100% = 0.0 KVA
					OTHER	0.9	85%	1.0	100% = 1.0 KVA
PHASE BALANCE	A-B	B-C	C-A	PF	KITCHEN	0.0	95%	0.0	125% = 0.0 KVA
	%	89	95	86	NONCONCIDE	0.0	95%	0.0	0% = 0.0 KVA
					PEAK LOAD	0.0	90%	0.0	125% = 0.0 KVA
					0 % SPAR	0.0	90%	0.0	100% = 0.0 KVA
					TOTAL	39.9		11.5 KVA	12.9 KVA



© 2021 all rights reserved

MIN PANEL IMPACTIVITY 35 1AMPERES

Version 0822

Generator ID: Gen											
NFPA 110	Level 2	Class 2	Type 60								
System Voltage:	277	/ 480	vols,	3	phase,	4	wire				
Elevation:	5,800	ft	derate	3	% per 1000 ft above	3,300	ft	=	93% deration factor for elevation		
Ambient temperature:	110	deg F,	43	deg C,	derate	1	% per 10°F above 77°F =	97%	temperature deration		
Net Elevation and Temperature Deration Factor =				89%	of nameplate rating						
loads:											
Sequence #1			Amps	kVA	PF	kW	Harmonic Load %/YN	Starting kVA Multiplier	Starting kW		
1 UPS			57.7	48.0	100%	48.0	Y	1.2	57.6		
2 PDU			57.7	48.0	100%	48.0	Y	1.2	57.6		
Sequence #1 Totals			115	96.0	100%	96.0	100%		115		
loads:											
Sequence #2			Amps	kVA	PF	kW	Harmonic Load %/YN	Starting kVA Multiplier	Starting kW		
1 CH-3			108	90.0	80%	72.0			180		
2 CHWP-6			4.8	4.0	98%	3.9			2.5	10.0	
3 CHWP-7			4.8	4.0	98%	3.9			2.5	10.0	
4 CONTROLS CIRCUIT			10.0	8.3	95%	7.9			20	16.6	
5 GLYCOL FEEDER			0.5	0.4	80%	0.3			6.0	2.3	
6 COMPUTER CIRCUITS			12.0	10.0	95%	9.5			20	19.9	
7 FREEZER 1			6.3	5.2	80%	4.2			3.0	15.7	
8 FREEZER 2			6.3	5.2	80%	4.2			3.0	15.7	
Sequence #2 Totals			153	127	83%	106			270		
Sequence 1 + 2 Totals			268	223	90%	202	48%		493		
Sequence Totals: 268 A, 223 kVA, 202 kW, 90% PF, 493 Starting kVA											
Spare	10%	26.8 A,	22.3 kVA,	20.2 kW,	90% PF,	49.3	Starting kVA				
Safety Factor	20%		49.1 kVA,	44.4 kW,	90% PF,	109	Starting kVA				
Percent Load Harmonics			48%								
Net generator size before deration											
	354 A,	294 kVA,	266 kW,	90% PF,	651	Starting kVA					
Net generator nameplate sizes after deration											
				Minimum Performance at Project Site			Minimum				
				Amps	kVA	PF	kW	Starting kVA			
				396	329	90%	298	651			



Image shown may not reflect actual configuration.

DG350 – DG500 Sound Attenuated Enclosures

US Sourced
Gas Generator Set
350 – 500 kW 60 Hz

Features

Robust/Highly Corrosion Resistant Construction

- Factory installed on skid base
- Environmentally friendly, polyester powder baked paint
- 14 gauge steel
- Interior zinc plated fasteners
- Exterior stainless steel fasteners
- Internally mounted exhaust silencing system
- Designed and tested to comply with UL 2200 Listed generator set package
- Steel enclosures designed for 150 mph
- Compression door latches providing solid door seal

Excellent Access

- Large cable entry area for installation ease
- Accommodates side mounted single or multiple breakers
- Three doors on both sides
- Vertically hinged allow 180° opening rotation and retention with door stays
- Coolant drains piped to the exterior of the enclosure base
- Radiator fill cover

Security and Safety

- Lockable access doors which give full access to control panel and breaker
- Cooling fan and battery charging alternator fully guarded
- Oil fill and battery can only be reached via lockable access
- Externally mounted emergency stop button
- Designed for spreader bar lifting to ensure safety
- Stub-up area is rodent proof


Transportability

These enclosures are of extremely rugged construction to withstand outdoor exposure and rough handling common on many construction sites.

Options

- Enclosure constructed with 14 gauge steel
- Enclosure constructed with 12 gauge aluminum (5052 grade)
- Caterpillar yellow or white paint
- Seismic certification per applicable building codes: IBC 2018, CBC 2007, CBC 2010
- IBC Certification for 180 mph wind loading[#]
- DC lighting package
- 5 kW Canopy space heater to facilitate compliance with NFPA 110
- Motorized louvers and gravity discharge damper
- 125A Load Center
- LHS or RHS or both mounted GFCI outlets

[#] Applicable to Aluminum Enclosures only.



Weights and Dimensions

Enclosure Type	Genset Model	Length "L"		Width "W"		Height "H"		Package Weight	
		mm	in	mm	in	mm	in	kg	lb
Sound Attenuated Level-2	DG350 to DG500	5245	206	2196	86	2251	89	6342	13982
Sound Attenuated Level-2 Cold Weather		5245	206	2196	86	2251	89	6475	14275
Weather Protective		5245	206	2196	86	2251	89	6114	13479
Sound Attenuated Level-2 (AI)		5245	206	2196	86	2251	89	5505	12136
Sound Attenuated Level-2 Cold Weather (AI)		5245	206	2196	86	2251	89	5812	12813

Enclosure Sound Pressure Levels (SPL) Targets for Sound Attenuated Steel and Aluminum Enclosures.

Genset Models	SPL at 7m (23 ft) at 100% load (L2) dBA
DG350 - DG500	75

(Consult your local Cat dealer for sound data. For deriving aluminum enclosure sound data, add 1 db to steel enclosure data from TMI).

LET’S DO THE WORK.™

Cat® DG350

Gas Generator Sets



Image shown might not reflect actual configuration

Engine Model	Cat® CG18 In-line 6, 4-cycle Natural Gas
Bore x Stroke	145 mm x 183 mm (5.7 in x 7.2 in)
Displacement	18.1 L (1106.3 in³)
Compression Ratio	10.5:1
Aspiration	Turbocharged, Air-to-Air Aftercooled
Fuel System	Venturi – Mixer
Governor	Electronic ADEM™ A4 - G2 Class* capable

Model	Standby / Demand Response Power	Emission Strategy
DG350	60 Hz	U.S. EPA Certified for Emergency and Non-Emergency
	350 ekW (437.5 kVA)	

PACKAGE PERFORMANCE

Performance	Standby	Demand Response
Performance Number	EM6247	EM6188
Frequency, Hz	60	
Genset power rating with fan @ 0.8 power factor, ekW	350	
Fuel Consumption		
Utility Fuel Pressure – Standard Pressure, psi [#]	1.25 – 1.5	
Utility Fuel Pressure – Low Pressure (optional), psi [#]	0.25 – 1.5	
100% load with fan, CFH (m³/hr)	3962 (112.2)	4110 (116.4)
75% load with fan, CFH (m³/hr)	3157 (89.4)	3277 (92.8)
50% load with fan, CFH (m³/hr)	2352 (66.6)	2433 (68.9)
Cooling System¹		
Radiator air flow restriction (system), kPa (in. water)	0.12 (0.48)	
Radiator air flow, CFM (m³/min)	24826 (703)	
Engine coolant capacity, L (gal)	27 (7.2)	
Radiator coolant capacity, L (gal)	62 (16.4)	
Total coolant capacity, L (gal)	89 (23.6)	
Inlet Air		
Combustion air inlet flow rate, lb/hr (m³/min)	4918 (31.7)	5231 (33.7)
Exhaust System		
Exhaust stack gas temperature, °C (°F)	550 (1022)	548 (1018)
Exhaust gas flow rate, lb/hr (m³/min)	5117 (92.8)	5427 (98.4)
Exhaust system backpressure (minimum allowable), kPa (in. water)	1 (4.02)	
Exhaust system backpressure (maximum allowable), kPa (in. water)	5 (20.1)	
Heat Rejection		
Heat rejection to coolant (total), kW (BTU/min)	142 (8075)	145 (8246)
Heat rejection to atmosphere to aftercooler, kW (BTU/min)	106 (6028)	122 (6938)
Heat rejection to atmosphere from engine, kW (BTU/min)	85 (4833)	86 (4890)
Heat rejection to exhaust (total), kW (BTU/min)	389 (22122)	411 (23373)

PACKAGE PERFORMANCE (contd.)


Lube System	
Sump Refill with Filter, L (gal)	42 (11.1)
Maximum oil temperature, °C (°F)	110 (230)

Emissions	Standby	Demand Response
Meets EPA Stationary Emergency and Non-Emergency Limits (g/bhp-hr)	NOx: 2.0 CO: 4.0 VOC: 1	NOx: 1.0 CO: 2.0 VOC: 0.7

ALTERNATOR DATA

Alternator²						
Duty Cycle		Standby/Demand Response				
Phase		3-Phase				
Voltages, V		480/277	240/139	208/120	240/120	600/346
Current, Amps		526	1053	1214	1053	421
Frame: LC6114B Excitation: SE	Temperature Rise @ 40°C	130	130	130	130	
	Motor Starting Capability @ 30% Voltage Dip, skVA	800	800	610	610	
Frame: LC6114C Excitation: SE	Temperature Rise @ 40°C	105	105			
	Motor Starting Capability @ 30% Voltage Dip, skVA	802	802			
Frame: LC6114D Excitation: SE	Temperature Rise @ 40°C	80	80	105	105	
	Motor Starting Capability @ 30% Voltage Dip, skVA	824	824	627	627	
Frame: LC6114F Excitation: SE	Temperature Rise @ 40°C			80	80	
	Motor Starting Capability @ 30% Voltage Dip, skVA			1001	1001	
Frame: LC6124B Excitation: AREP	Temperature Rise @ 40°C					130
	Motor Starting Capability @ 30% Voltage Dip, skVA					849
Frame: LC6124D Excitation: AREP	Temperature Rise @ 40°C					80
	Motor Starting Capability @ 30% Voltage Dip, skVA					1287

WEIGHTS & DIMENSIONS



On Narrow Skid Base

Length "A" mm (in)	Width "B" mm (in)	Height "C" mm (in)	Dry Weight kg (lb)
3593 (141.4)	1766 (69.5)	2087 (82.1)	4689 (10337)

On Wide Skid Base

Length "A" mm (in)	Width "B" mm (in)	Height "C" mm (in)	Dry Weight kg (lb)
4986 (196.2)	2170 (85.4)	2089 (82.2)	5017 (11060)

Note: General configuration not to be used for installation. See general dimension drawings for detail.

APPLICABLE CODES AND STANDARDS:

CSA C22.2 No 100-04, UL 489, UL 869, UL 2200, IBC, IEC60034-1, ISO 3046, ISO 8528, NEMA MG 1-22, NEMA MG 1-33 and facilitates the compliance to NFPA 37, NFPA 70, NFPA 99, NFPA 110.

Codes may not be available for all model configurations. Site level review needed for NFPA70. Please consult your Cat dealer for availability.

STANDBY POWER: Output available with varying load for the duration of the interruption of the normal source power. Average power output is 70% of the standby rated kW. Typical operation is 200 hours per year, with maximum expected usage of 500 hours per year.

DEMAND RESPONSE POWER: Output available with varying load when participating in a demand response or economic dispatch program. Average power output is 70% of the standby rated kW. Typical operation is 200 hours per year, with maximum expected usage of 500 hours per year.

Ratings are based on SAE J1349 standard conditions. These ratings also apply at ISO 3046 standard conditions.

1 CFH = 1000 BTU/HR

Fuel Rates are based on LHV (lower heat values) of 905 BTU/SCF for Natural Gas @77°F (25°C) and 498.6 ft (152m) above sea level.

Additional ratings may be available for specific customer requirements. For higher temperatures and elevations follow derate specification. Contact your Cat representative for details.

DEFINITIONS AND CONDITIONS

1 For ambient and altitude capabilities consult your Cat dealer.

Air flow restriction (system) is added to the existing restriction from the factory.

2 Generator temperature rise is based on a 40°C (104°F) ambient per NEMA MG1-32.

Operating Fuel Pressure is the fuel pressure required to be delivered at the genset base frame rail connection. Recommended gas regulator to be used in conjunction if the gas supply pressure is above this range.

* Governing Class capability as per ISO-8528-5. Consult your local Cat dealer for configuration and site specific transient performance classification.

LET'S DO THE WORK.™

CAT

Project Sizing Report

Sizing Id

11246512

Project Name

RRCC Gen 2

Customer Name

RMH Group

Region

U.S.

Prepared By

Anthony Andrade

Modified Date

27-Oct-2025

Electricity Supply

60 Hz 480/277 V

Connection

STAR

Max. Ambient Temperature

109.0 F

Altitude

5,800.0 Ft. A.S.L

Humidity

30%

Project Description

Load Analysis Summary

Max Transient Load Step

397.5 SkVA / 135.2 SkW

Peak Transient Load Step

397.5 SkVA / 155.0 SkW

Final Running Load

248.1 kVA / 221.6 kW / 0.89 PF

Max Running Non Linear Load

173.6 RkVA

Selection Criteria

Step 1 Voltage dip restriction

Project THDI

10.4%

Note: The selected gas generator set performance may vary when applying a UPS ramp load to this generator set. To ensure proper operation, please contact your local Cat Dealer or Caterpillar A&I team.

Generator Set

Engine Model

(1) of CG18

Package Model

DG350

Voltage Regulator and Slope

Standard 2:1 slope;

Feature Code

18LGE05

Fuel

Natural Gas

Sizing Methodology

Conventional

Methane #

84.70

Generator Set Type

Stationary

Nameplate Rating

350.0 ekW / 437.5 kVA / 0.8 PF

Site Output Rating

350 ekW / 437.5 kVA

Rating Type

Standby

Open / Enclosure

Open

UL Listed

UL Listed

Capacity Used

63.3%

Project THDV

5.8%


Engine			
Make / Model	CG18	Emissions / Certifications	US EPA S.I. Stationary Emergency
Aspiration	TA	Governor	ADEM4 W/ IM
Cylinder Configuration	INLINE - 6	Aftercooler Type	ATAAC
Speed	1800 RPM	Displacement	1,106 Cubic Inch / 18 Liter
Engine Performance Number	EM6247	Bore	145
Fuel Consumption at 100% Load	0.0 scfm	Stroke	183

Alternator			
Alternator Type/Frame Size	LC / LC6134C	Insulation Class	H
Alternator Winding Pitch	0.6667	Temperature Rise	105 C
Excitation/Winding Type	PM / RANDOM	Number Of Poles	4
Alternator Arrangement Number	6122018	Number of Leads	12
Subtransient Reactance X"d	0.1413	Rated Amps	526.2

**** See your Caterpillar dealer and/or Spec Sheet for technical information.


***** Package Power Tolerance: +/- 5%

Block Load(Only) Transient Response *			
Load Change %	FDip %	VDip %	Recovery Time (sec)
25	5.2	7.7	<3
50	10.5	18.3	<5
75	15.3	28.0	<5
100	21.4	40.5	7



Transient Performance

Block Load (only) Transient Response values are at factory conditions with a heat-soaked, unloaded engine and application of a resistive load. This information is representative of a typical Cat generator set, but is not guaranteed. Generator set block load capabilities at site conditions may vary from factory transient response test results due to initial engine state, site altitude, site ambient, and engine to engine variation.

		Load Report													
Project Name		RRCC Gen 2				Electricity Supply				60 Hz 480/277 V					
Customer Name		RMH Group				Rating Type				Standby					
Region		U.S.				Max. Ambient Temperature				109.0 F					
Prepared By		Anthony Andrade				Altitude				5,800.0 Ft. A.S.L					
Modified Date		27-Oct-2025				Humidity				30%					
Engine Model		(1) of CG18				Nameplate Rating				350.0 ekW / 437.5 kVA / 0.8 PF					
Load Details				Permitted		Predicted		Transient Inrush		Running		Resultant Peak		Cumulative Running	
Load Step	Load Description			FDip	VDip	FDip	VDip	SkVA	SkW	kVA	kW	SkVA	SkW	kVA	kW
Step 1															
1.1	1x70.13 HP - Three Phase Motor Load: NEMA, 3-Phase Motor, Across the line, Loaded			30%	30%			397.5	135.2	63.2	56.2				
Step 1 Total				30%	30%	7.6%	15.0%	397.5	135.2	63.2	56.2				
Total Through Step 1												397.5	135.2	63.2	56.2
Step 2															
2.1	1x5.00 HP - Three Phase Motor Load: NEMA, 3-Phase Motor, Across the line, Loaded, NEMA H			30%	30%			33.5	19.1	5.6	4.4				
2.2	1x5.00 HP - Three Phase Motor Load: NEMA, 3-Phase Motor, Across the line, Loaded, NEMA H			30%	30%			33.5	19.1	5.6	4.4				
2.3	1x12.00 Amps - Office Equipment Load: Office Equipment, Distr. 3-Phase , 46.7 THDI%			30%	30%			10.0	9.0	10.0	9.0				
2.4	1x10.00 Amps - Office Equipment Load: Office Equipment, Distr. 3-Phase , 46.7 THDI%			30%	30%			8.3	7.5	8.3	7.5				
2.5	1x0.25 HP - Three Phase Motor Load: NEMA, 3-Phase Motor, Across the line, Loaded, NEMA M			30%	30%			5.3	4.0	0.4	0.3				
2.6	1x3.00 HP - Three Phase Motor Load: NEMA, 3-Phase Motor, VFD, 110% Current Limit, Single Operating Point, 6 Pulse , 29.1 THDI%			20%	20%			0.3	0.3	3.4	3.0				
2.7	1x3.00 HP - Three Phase Motor Load: NEMA, 3-Phase Motor, VFD, 110% Current Limit, Single Operating Point, 6 Pulse , 29.1 THDI%			20%	20%			0.3	0.3	3.4	3.0				

2.8	1x100.00 kW - UPS Load: User Defined UPS, 3-Phase, IGBT, 25% Walk-In, 25% Battery Recharge, No Battery Revert , 6.7 THDI%	10%	10%			37.1	33.4	148.5	133.7				
Step 2 Total		10%	10%	6.0%	9.4%	124.4	92.7	248.1	221.6				
Total Through Step 2										192.8	155.0	248.1	221.6
Load Analysis Summary : Generator set is user selected and meets site requirements													
						Maximum Step				Maximum Peak		Final Running	
						SkVA	SkW			SkVA	SkW	kVA	kW
						397.5	135.2			397.5	155.0	248.1	221.6